

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

ORIGINAL

Operator: License # 33428
Name: Fort Scott Methane Partners, LLC
Address: 2329 West Main St., #200
City/State/Zip: Littleton, CO 80120
Purchaser: SIGW, waiting on pipeline
Operator Contact Person: Larry Weis
Phone: (303) 895-7178
Contractor: Name: Mokat Drilling
License: 5831
Wellsite Geologist: Larry Weis

KCC

DEC 12 2005

CONFIDENTIAL

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

8-26-05	8-27-05	10-4-05
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 15-011-23133-00-00
County: Bourbon
SW SW NE Sec. 15 Twp. 27 S. R. 22 East West
2300' feet from S / (N) (circle one) Line of Section
2300' feet from (E) / W (circle one) Line of Section


Footages Calculated from Nearest Outside Section Corner:
(circle one) (NE) SE NW SW
Lease Name: O'Brien Well #: 15-32
Field Name: Wildcat
Producing Formation: Cherokee Coals
Elevation: Ground: 962' Kelly Bushing: _____
Total Depth: 745' Plug Back Total Depth: 742'
Amount of Surface Pipe Set and Cemented at 22' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 742'
feet depth to surface w/ 85 sx cm.

Drilling Fluid Management Plan ALT II WITH
(Data must be collected from the Reserve Pit) 4-3-07
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used air drilled
Location of fluid disposal if hauled offsite: LC 132
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Geologist Date: 12-12-05
Subscribed and sworn to before me this 12th day of December,
20 05.
Notary Public: [Signature]
Date Commission Expires: _____



KCC Office Use ONLY
YES Letter of Confidentiality Received
If Denied, Yes Date: _____
_____ Wireline Log Received
_____ Geologist Report Received
_____ UIC Distribution

X

CONFIDENTIAL

Side Two

ORIGINAL

Operator Name: Fort Scott Methane Partners, LLC Lease Name: O'Brien Well #: 15-32
Sec. 15 Twp. 27 S. R. 22 [X] East [] West County: Bourbon

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken [] Yes [X] No (Attach Additional Sheets)

Samples Sent to Geological Survey [] Yes [X] No

Cores Taken [] Yes [X] No

Electric Log Run [X] Yes [] No (Submit Copy)

List All E. Logs Run:

Compensated Density/Neutron, Dual Induction, Cement Bond Log

Table with 3 columns: Name, Top, Datum. Rows include Pawnee Lime (146', +816'), Oswego Lime (229', +733'), Bevier Coal (354', +608'), Riverton Coal (647', +324'), Mississippian (666', +315').

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Rows for Surface and Production.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD - Bridge Plugs Set/Type table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Includes KCC stamp and DEC 12 2005 date.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run, Date of First, Resumerd Production, SWD or Enhr., Producing Method, Estimated Production Per 24 Hours, Oil Bbbs., Gas Mcf, Water Bbbs., Gas-Oil Ratio, Gravity.

Disposition of Gas table with columns: METHOD OF COMPLETION, Production Interval. Includes checkboxes for Vented, Solid, Used on Lease, Open Hole, Perf., Dually Comp., Commingled.

CONSOLIDATED OIL WELL SERVICES, INC.
 211 W. 14TH STREET, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

CONFIDENTIAL

TICKET NUMBER 5299
 LOCATION FWEKa
 FOREMAN Brad Butler

**TREATMENT REPORT & FIELD TICKET
 CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-31-05		O'Brien 15-32	15	27s	22E	Bourbon
CUSTOMER FortScott Methane Partners LLC			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 2329 W. Main ST. # 200			446	Scott		
CITY STATE ZIP CODE Littleton CO 80120			441	Justin		
			452-T63	Larry		

JOB TYPE Logstring HOLE SIZE 6 3/4" HOLE DEPTH 745' CASING SIZE & WEIGHT 4 1/2" 10.5 lb
 CASING DEPTH 742' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.2 lb SLURRY VOL 25 Bbl. WATER gal/sk 8.0 CEMENT LEFT in CASING 0'
 DISPLACEMENT 11 3/4 Bbls DISPLACEMENT PSI 350 ~~900~~ PSI 900 Landed Plug RATE 4BPM-2BPM

REMARKS: Safety Meeting: Rig up to 4 1/2" casing, Break circulation with 20 Bbls water.
Pumped 8 Bbl. Gel Flush, 10 Bbl. water Spacer, 10 Bbl. Metasilicate, 5 Bbl. water Spacer.
Mixed 85 sks. ThickSet cement w/ 4# P/SK of K01-SEAL @ 13.2 1/2 P/GAL.
Shut down - wash out pump & lines - Release Plug - Displace Plug with 11 3/4 Bbls water.
Final pumping @ 350 PSI - Bumped Plug to 900 PSI - wait 2 min - Release Pressure
Float Held - close casing in with 0 PSI
Good cement returns to surface with 6 Bbl. slurry
Job complete - Teardown

Thank You

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	765.00	765.00
5406	0	MILEAGE Truck Infield	2.50	N/C
1126A	85 SKS	ThickSet cement	13.00	1105.00
1110A	7 SKS	K01-SEAL 4# P/SK	16.90	118.30
1118A	3 SKS	Gel Flush	6.63	19.89
1111A	50 lbs	Metasilicate PreFlush	1.55 lb.	77.50
5407A	4.68 TON	60 miles- Bulk Truck	.92	258.34
5501C	4 Hrs	Water Transport	88.00	352.00
1123	5000 GAL	City water	12.20	61.00
4404	1	4 1/2" Top Rubber Plug	38.00	38.00
			6.3%	SALES TAX
				ESTIMATED TOTAL
				89.44
				2884.41

AUTHORIZATION [Signature] TITLE _____ DATE _____

