

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED
KANSAS CORPORATION COMMISSION
FORM ACO-1
September 1999
Must Be Typed
JUN 01 2004

WELL COMPLETION FORM

CONFIDENTIAL

WELL HISTORY - DESCRIPTION OF WELL & LEASE

CONSERVATION DIVISION

ORIGINAL

Operator: License # 5254
Name: MIDCO Exploration, Inc.
Address: 414 PLAZA DRIVE, SUITE 204
City/State/Zip: WESTMONT, IL 60559
Purchaser: ONEOK
Operator Contact Person: Earl J. Joyce, Jr.
Phone: (630) 655-2198
Contractor: Name: Duke Drilling Co., Inc.
License: 5929
Wellsite Geologist: N/A **KCC**

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____
4/8/04 4/14/04 4/29/04
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15-095-21872-0000
County: Kingman
SW .NW .SE . Sec. 27 Twp. 28 S. R. 8 East West
1650 feet from (S) N (circle one) Line of Section
2310 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE (SE) NW SW
Lease Name: Covington Well #: 3
Field Name: Garlisch

Producing Formation: Mississippi
Elevation: Ground: 1641' Kelly Bushing: 1649'
Total Depth: 4485' Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 283 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.
ACT I W/H M 2-22-07

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 31,000 ppm Fluid volume 790 bbls
Dewatering method used vacuumed capturable fluids
Location of fluid disposal if hauled offsite:
Operator Name: Messenger Petroleum, Inc.
Lease Name: Nicholas SWD License No.: 4706
Quarter NE Sec. 20 Twp. 30 S. R. 8 East West
County: Kingman Docket No.: 25,073

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Vice-President Date: 5/27/2004
Subscribed and sworn to before me this 27th day of May, 2004

19 _____
Notary Public: Nancy L. Macyunas "OFFICIAL SEAL"
Nancy L. Macyunas
Notary Public, State of Illinois
My Commission Exp. 06/24/2006
Date Commission Expires: _____

KCC Office Use ONLY
Yes Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

✓

X

CONFIDENTIAL

Side Two

ORIGINAL

Operator Name: MIDCO EXPLORATION, INC. Lease Name: COVINGTON Well #: 3
Sec. 27 Twp. 28 S. R. 8 East West County: Kingman

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No

List All E. Logs Run: Dual Induction, Dual Compensated Porosity, Microresistivity, Borehole Compensated Sonic, Cement Bond

Log Formation (Top), Depth and Datum Sample

Table with 3 columns: Name, Top, Datum. Rows include Heebner, Toronto, Lansing, Mississippi Chert, Viola.

KCC MAY 17 2004

RECEIVED KANSAS CORPORATION COMMISSION JUN 01 2004

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set, Weight Lbs./Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD - Bridge Plugs Set/Type table with columns: Shots Per Foot, PERFORATION RECORD, Acid, Fracture, Shot, Cement Squeeze Record, Depth.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run, Date of First, Resumed Production, SWD or Enhr., Producing Method, Estimated Production Per 24 Hours, Oil Bbls., Gas Mcf, Water Bbls., Gas-Oil Ratio, Gravity.

Disposition of Gas METHOD OF COMPLETION Production Interval. Includes checkboxes for Vented, Sold, Used on Lease, Open Hole, Perf., Dually Comp., Commingled, Other.

ALLIED CEMENTING CO., INC.

CONFIDENTIAL
KCC RECEIVED COMMISSION
15141

BOX 31
MAY 27 2004
JUN 01 2004
SERVICE POINT: Med Lodge

OSSELL, KANSAS 67665
CONFIDENTIAL CONSERVATION DIVISION

-15-04	SEC. 27	TWP. 28S	RANGE 8W	CALLED OUT WICHITA 1:30 PM	ON LOCATION 3:30 PM	JOB START 8:15 PM	JOB FINISH 8:45 PM
Covington WELL # 3			LOCATION Spivey Bull Park	1 to		COUNTY Kingman	STATE KS
OLD OR NEW (Circle one)			Stop sign 2 1/4 N W/S				

CONTRACTOR Duke #2

TYPE OF JOB Production

HOLE SIZE 7 7/8 T.D. 4485

CASING SIZE 4 1/2 x 10.5 DEPTH 4252

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL latch down Bottle DEPTH 4210

PRES. MAX 1800 MINIMUM _____

MEAS. LINE _____ SHOE JOINT 42

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 67 BBLs 2% KCL water

EQUIPMENT

PUMP TRUCK CEMENTER Justin Hunt

372 HELPER Mark Brungardt

BULK TRUCK _____

353 DRIVER Darin Franklin

BULK TRUCK _____

_____ DRIVER _____

OWNER Midco Exploration

CEMENT

AMOUNT ORDERED 190 5% ASC + 5# Kd-seal + 62% Gas Block

Gel	<u>1</u>	@	11.00	11.00
COMMON	<u>15</u>	@	7.65	114.75
POZMIX	<u>10</u>	@	4.00	40.00
GEL Gas Block	<u>89#</u>	@	7.00	623.00
CHLORIDE 25#		@		
Kal-Seal	<u>950#</u>	@	.50	475.00
ASC	<u>190</u>	@	9.50	1805.00
ASF	<u>500 gal</u>	@	1.00	500.00
Mud Clean C	<u>500 gal</u>	@	1.00	500.00
Clapro	<u>7 gal</u>	@	22.90	160.30
HANDLING	<u>269</u>	@	1.25	336.25
MILEAGE	<u>269 x .35</u>	@	4.05	470.75
TOTAL				<u>5036.05</u>

REMARKS:

Pipe on BTM Break Circ
 Drop Ball Set Tacker Shoe & Circulate
 3 BBLs H₂O - 500 gals Mud Clean C
 500 gals ASF - 3 BBLs H₂O
 Plug Rat + Mouse 25% x 40.40.4
 190 5% ASC @ 4.5#
 Release Plug Disp 67 BBLs 2% KCL
 Land Plug 400 - 1000# Release PSI
 Flat Held

SERVICE

DEPTH OF JOB	<u>4252</u>			
PUMP TRUCK CHARGE			<u>1195.00</u>	
EXTRA FOOTAGE		@		
MILEAGE	<u>35</u>	@	<u>4.00</u> 140.00	
PLUG		@		
		@		
		@		
		@		
TOTAL				<u>1335.00</u>

CHARGE TO: Midco Exploration

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

<u>4/2</u> Tacker Shoe	@	<u>1325.00</u>	1325.00	
latch down, Plug	@	<u>300.00</u>	300.00	
5 Turbolizers	@	<u>55.00</u>	275.00	
5 Centralizers	@	<u>45.00</u>	225.00	
	@			
TOTAL				<u>2125.00</u>

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE ~~5036.05~~

DISCOUNT ~~5036.05~~ IF PAID IN 30 DAYS

SIGNATURE David J. Mayfield

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

PRINTED NAME _____

CONFIDENTIAL

ORIGINAL

ALLIED CEMENTING CO., INC.

15181

P.O. BOX 31
RUSSELL, KANSAS 67665

KCC

JUN 11 2004

MAY 27 2004

CONSERVATION DIVISION
WICHITA, KS

SERVICE POINT:

Medicine Lodge

CONFIDENTIAL

1-8-04	SEC. 27	TWP. 28S	RANGE 8W	CALLED OUT 2:00 pm	ON LOCATION 4:00 pm	JOB START 6:15 pm	JOB FINISH 6:30 pm
WELL # 3		LOCATION Spivey Ball Park North		COUNTY Kingman		STATE KS,	
D OR NEW (Circle one)		to stop sign 2 1/4 N, W/S					

CONTRACTOR Doke #2
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D.
 CASING SIZE 8 7/8 DEPTH 283'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX 200 MINIMUM —
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG. 15'
 PERFS.
 DISPLACEMENT 17 Bbls Freshwater
 EQUIPMENT

OWNER Midco Exploration
 CEMENT
 AMOUNT ORDERED
225 sx 60:40:2% gel + 3% cc
 COMMON A 135 sx @ 7.65 1032.75
 POZMIX 90 sx @ 4.00 360.00
 GEL 4 sx @ 11.00 44.00
 CHLORIDE 7 sx @ 30.00 210.00
 @
 @
 @
 @
 @
 @
 HANDLING 236 @ 1.25 295.00
 MILEAGE 35 x .05 x 236 413.00
 TOTAL 2354.75

PUMP TRUCK CEMENTER Carl Balding
 # 358-265 HELPER Bill Mackadoo
 BULK TRUCK
 # 359-250 DRIVER THAD Cantrell
 BULK TRUCK
 # DRIVER

REMARKS:

SERVICE

Start 3 Bbls Freshwater, mix 225 sx 60:40:2+3%cc, Release plug + disp w/ 17 Bbls Freshwater, leave 15' Cement in casing + shut in.
circulate 75 sx to pit

DEPTH OF JOB 283'
 PUMP TRUCK CHARGE 520.00
 EXTRA FOOTAGE @
 MILEAGE 35 @ 4.00 140.00
 PLUG wooden @ 45.00
 @
 @

TOTAL 705.00

CHARGE TO: Midco Exploration
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE ~~605.00~~
 DISCOUNT ~~605.00~~ IF PAID IN 30 DAYS

SIGNATURE David Mayfield

PRINTED NAME _____

ANY APPLICABLE TAX
 WILL BE CHARGED
 UPON INVOICING