

ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

CONFIDENTIAL

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 33476
 Name: FIML Natural Resources, LLC
 Address: 410 17th St. Suite 900
 City/State/Zip: Denver, CO 80202
 Purchaser: NCRA
 Operator Contact Person: Phyllis Sobotik
 Phone: (303) 899-5608
 Contractor: Name: Excell Services, Inc.
 License: 8273
 Wellsite Geologist: _____
 Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
 If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>12/28/05</u>	<u>1/4/06</u>	<u>1/30/06</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 171-20606 0000
 County: Scott
SE SW Sec. 4 Twp. 19S S. R. 31 East West
660 feet from 3 / N (circle one) Line of Section
1980 feet from E / N (circle one) Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE SE NW SW
 Lease Name: Pfeifer Ball Well #: 14-4-1931
 Field Name: Wildcat
 Producing Formation: Mississippian Spergen
 Elevation: Ground: 2973' Kelly Bushing: 2985'
 Total Depth: 4751' Plug Back Total Depth: 4723'
 Amount of Surface Pipe Set and Cemented at 8 jts 8 5/8" csg @ 357 Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set DV tool @ 2998 Feet
 If Alternate II completion, cement circulated from 2998
 feet depth to surface w/ 545 sx cmt.
ALT II w/ 4-12-07

Drilling Fluid Management Plan
 (Data must be collected from the Reserve Pit)
 Chloride content 1600 ppm Fluid volume 1050 bbls
 Dewatering method used Evaporation
 Location of fluid disposal if hauled offsite: _____
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter: _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Phyllis Sobotik
 Title: Operations Regulatory Manager Date: 3/16/2006
 Subscribed and sworn to before me this 16th day of March,
2006
 Notary Public: Elaine Weirich
 Date Commission Expires: 5/5/2009

CONFIDENTIAL
KCC Office Use ONLY
 Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
MAR 10 2006
KCC RECEIVED
MAR 20 2006
KCC WICHITA

Operator Name: FIML Natural Resources, LLC Lease Name: Pfeifer Ball
 Sec. 4 Twp. 19S S. R. 31 East West County: Scott

JAN 13 1931

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Triple Combo; Microlog; Long Spaced Sonic	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td><input checked="" type="checkbox"/> Log</td> <td>Formation (Top), Depth and Datum</td> <td><input type="checkbox"/> Sample</td> </tr> <tr> <td>Name</td> <td>Top</td> <td>Datum</td> </tr> <tr> <td>Hutch-Salt</td> <td>2604'</td> <td>381'</td> </tr> <tr> <td>Topeka</td> <td>3527'</td> <td>-542'</td> </tr> <tr> <td>Toronto</td> <td>3931'</td> <td>-946'</td> </tr> <tr> <td>Lansing</td> <td>3960'</td> <td>-975'</td> </tr> <tr> <td>Mississippian</td> <td>4595'</td> <td>-1610'</td> </tr> </table>	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample	Name	Top	Datum	Hutch-Salt	2604'	381'	Topeka	3527'	-542'	Toronto	3931'	-946'	Lansing	3960'	-975'	Mississippian	4595'	-1610'
<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample																				
Name	Top	Datum																				
Hutch-Salt	2604'	381'																				
Topeka	3527'	-542'																				
Toronto	3931'	-946'																				
Lansing	3960'	-975'																				
Mississippian	4595'	-1610'																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24#	357'	Class A	225	3% CC, 2% gel
Production	7-7/8"	5-1/2"	15.5#	4748'	ASC	315	10% slt, 2% gel
				2998' DV	Lite	545	.5pps Flocele

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4620'-4624'	A/ 250 gals 15% MCA Acid, 250 gal 2% KCL water	4620'-24'

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-7/8"	4709'	NA	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. 2/15/06			Producing Method		
			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	22		42		

Disposition of Gas Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled 4620-24'
(If vented, Sumit ACO-18.) Other (Specify) _____

Allied Cementing Co., Inc
P.O. Box 31

JAN 03 2006

* I N V O I C E *

Russell, KS 67662 **CONFIDENTIAL**

MAR 16 2006

Invoice Number: 100046

KCC

Invoice Date: 12/29/05

Sold FIML Natural Resources
To: L.L.C.
410 17th St. #900
Denver, CO
80202

Cust I.D.....: FIML
P.O. Number...: Pfeifer/Ball #14-4-1931
P.O. Date.....: 12/29/05

Due Date.: 01/28/06
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	225.00	SKS	10.0000	2250.00	T
Gel	4.00	SKS	14.0000	56.00	T
Chloride	8.00	SKS	38.0000	304.00	T
Handling	237.00	SKS	1.6000	379.20	E
Mileage	60.00	MILE	14.2200	853.20	E
237 sks @.06 per sk per mi					
Surface	1.00	JOB	670.0000	670.00	E
Mileage pmp trk	60.00	MILE	5.0000	300.00	E
Guide Shoe	1.00	EACH	235.0000	235.00	T
Centralizers	3.00	EACH	55.0000	165.00	T
Surface Plug	1.00	EACH	45.0000	45.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 525.74
ONLY if paid within 30 days from Invoice Date

Subtotal: 5257.40
Tax.....: 192.47
Payments: 0.00
Total....: 5449.87

(5257.4)
4924.13

8100-145
Adam D. Bl...
D05192

RECEIVED
MAR 20 2006
KCC WICHITA

ALLIED CEMENTING CO., INC. 21846

Federal ~~CONFIDENTIAL~~ 27860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

MAR 16 2006

SERVICE POINT:

Oakley

DATE <u>12-28-05</u>	SEC. <u>4</u>	TWP. <u>19s</u>	RANGE <u>31w</u>	KCC CALLED OUT	ON LOCATION <u>9:10 AM</u>	JOB START <u>11:30 PM</u>	JOB FINISH <u>2:00 PM</u>
LEASE <u>Pfeifer-Bell</u>	WELL # <u>14-4-1931</u>	LOCATION <u>SCOTT CITY 8 E 4 3/4 S 1/2 E 1/2 N 2W</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Excell Drilling Rig 3

TYPE OF JOB Surface

HOLE SIZE <u>12 1/4</u>	T.D. <u>363'</u>
CASING SIZE <u>8 7/8</u>	DEPTH <u>355'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG. <u>15'</u>	
PERFS.	
DISPLACEMENT <u>2 1/2 Bbls</u>	

EQUIPMENT

OWNER Same

CEMENT AMOUNT ORDERED 225 sks com 37 cc 290 Gel

COMMON <u>225 sks</u>	@ <u>10.00</u>	<u>2250.00</u>
POZMIX	@	
GEL <u>4 sks</u>	@ <u>14.00</u>	<u>56.00</u>
CHLORIDE <u>8 sks</u>	@ <u>38.00</u>	<u>304.00</u>
ASC	@	
	@	
	@	
	@	
	@	
	@	
	@	
	@	
HANDLING <u>237 sks</u>	@ <u>1.60</u>	<u>379.20</u>
MILEAGE <u>6.4 / sk / mile</u>		<u>839.20</u>
TOTAL		<u>3842.40</u>

REMARKS:

Cement did circulate

Thank you.

CHARGE TO: FML Natural Resources L.L.C.

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>670.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>60 miles</u>	@ <u>5.00</u>	<u>300.00</u>
MANIFOLD	@	
	@	

RECEIVED
MAR 20 2006

KCC WICHITA

0 5/8

PLUG & FLOAT EQUIPMENT

<u>Guide shoe</u>	@	<u>235.00</u>
<u>3- Centralizers</u>	@ <u>55.00</u>	<u>165.00</u>
<u>1 8 5/8 Surface Plug</u>	@	<u>45.00</u>
	@	
	@	
TOTAL		<u>445.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE 445.00

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE

[Handwritten Signature]

W Gary Dole

PRINTED NAME

Well-File

CONFIDENTIAL

MAR 16 2006

KCC

* I N V O I C E *

Allied Cementing Co., Inc
P.O. Box 31
Russell, KS 67665

Invoice Number: 100215

Invoice Date: 01/12/06

RECEIVED
JAN 18 2006

Sold FIML Natural Resources
To: L.L.C.
410 17th St. #900
Denver, CO
80202

Cust I.D.....: FIML
P.O. Number...: Pfeifer/Ball 14-4-1931
P.O. Date.....: 01/12/06 ~~4-14-1931~~

Due Date.: 02/11/06
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Gel	6.00	SKS	14.0000	84.00	T
ASC	315.00	SKS	11.6500	3669.75	T
Salt	34.00	SKS	15.7500	535.50	T
WFR-2	500.00	GAL	1.0000	500.00	T
Handling	355.00	SKS	1.6000	568.00	E
Mileage	60.00	MILE	21.3000	1278.00	E
355 sks #@.06 per sk per mi		JOB	1320.0000	1320.00	E
Bottom Stage	1.00	MILE	5.0000	300.00	E
Mileage pmp trk	60.00	EACH	160.0000	160.00	T
Guide Shoe	1.00	EACH	265.0000	265.00	T
Float Collar	1.00	EACH	50.0000	1000.00	T
Centralizers	20.00	EACH	140.0000	140.00	T
Basket	1.00	EACH	3300.0000	3300.00	T
DV Tool	1.00	EACH	20.0000	20.00	T
Limit Clamp	1.00				

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 1214.02
ONLY if paid within 30 days from Invoice Date

Subtotal: 13140.25
Tax.....: 609.48
Payments: 0.00
Total....: 13749.73

8200-118
Adam D. Blum
1st stage

RECEIVED
MAR 20 2006
KCC WICHITA

ALLIED CEMENTING CO., INC. 13588

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT:

OAKLEY

MAR 16 2006

DATE <u>1-5-06</u>	SEC. <u>4</u>	TWP. <u>19S</u>	RANGE <u>31W</u>	CALLED OUT <u>KCC</u>	ON LOCATION <u>10:15 AM</u>	JOB START <u>2:45 PM</u>	JOB FINISH <u>3:45 PM</u>
LEASE <u>PFEIFERT</u>	WELL # <u>4-14-1931</u>	LOCATION <u>SCOTT CITY 8E-4 1/2 S-1/2 E-34W</u>			COUNTY <u>SCOTT</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR <u>EXCEL DRILL REC #3</u>	OWNER <u>SAME</u>
TYPE OF JOB <u>Production string "Bottom Stage"</u>	
HOLE SIZE <u>7 7/8"</u>	T.D. <u>4747.69'</u>
CASING SIZE <u>5 1/2"</u>	DEPTH <u>4747.69'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>D-U Tool</u>	DEPTH <u>3032.84'</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>21.54'</u>
CEMENT LEFT IN CSG. <u>21.54'</u>	
PERFS.	
DISPLACEMENT <u>40 BBL WATER 72 BBL MUD</u>	
EQUIPMENT <u>Total 112 BBL</u>	
PUMP TRUCK # <u>191</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE MAX</u>
BULK TRUCK # <u>386</u>	DRIVER <u>LARRY</u>
BULK TRUCK #	DRIVER

CEMENT		
AMOUNT ORDERED		
<u>315 SKS ASC 10% SALT 2% GEL</u>		
<u>500 GAL WFR-2</u>		
COMMON	@	
POZMIX	@	
GEL <u>6 SKS</u>	@ <u>14.00</u>	<u>84.00</u>
CHLORIDE	@	
<u>ASC 315 SKS</u>	@ <u>11.65</u>	<u>3669.75</u>
<u>SALT 34 SKS</u>	@ <u>15.75</u>	<u>535.50</u>
<u>WFR-2 500 GAL</u>	@ <u>1.00</u>	<u>500.00</u>
HANDLING <u>355 SKS</u>	@ <u>1.60</u>	<u>568.00</u>
MILEAGE <u>66¢ PER SK/MILE</u>		<u>1278.00</u>
TOTAL		<u>6635.25</u>

REMARKS:

MIX 500 GAL WFR-2 315 SKS
ASC 10% SALT 2% GEL. WASH TRUCK
& LENSES. DISPLACE 40 BBL WATER
72 BBL mud. Plug landed AT
1800 PSE. FLOAT HELD.

DROP Bomb WAIT 20 MIN. OPEN
D-U Tool 800 PSE. CIRCULATE HRS.

THANK YOU

SERVICE

DEPTH OF JOB	<u>4747.69'</u>	
PUMP TRUCK CHARGE		<u>1520.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>60 MI</u>	@ <u>5.00</u>	<u>300.00</u>
PLUG	@	
<u>RECEIVED</u>		
<u>MAR 20 2006</u>		
TOTAL		<u>1620.00</u>

CHARGE TO: FIML NATURAL RESOURCES LLC.

STREET _____
CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

KCC WICHITA

5 1/2" FLOAT EQUIPMENT

<u>1-GUIDE SHOE</u>		<u>160.00</u>
<u>1-BIT SAVER FLOAT COLLAR</u>		<u>265.00</u>
<u>20-CENTRALIZERS</u>	@ <u>50.00</u>	<u>1000.00</u>
<u>1-BASKET</u>	@	<u>140.00</u>
<u>1-D-U TOOL</u>	@	<u>3300.00</u>
<u>1-LENET CLAMP</u>	@	<u>20.00</u>
TOTAL		<u>4885.00</u>

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

Well file

CONFIDENTIAL

MAR 16 2006

KCC

* INVOICE *

Allied Cementing Co., Inc
P.O. Box 31

Russell, KS 67665

Invoice Number: 100216

Invoice Date: 01/12/06

RECEIVED
JAN 18 2006

Sold FIML Natural Resources
To: L.L.C.
410 17th St. #900
Denver, CO
80202

Cust I.D.....: FIML
P.O. Number...: Pfeifer-Ball 14-4-1931
P.O. Date.....: 01/12/06 4-14-1931

Due Date.: 02/11/06
Terms....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Lite	545.00	SKS	8.8000	4796.00	T
Gilsonite	2725.00	SKS	0.6000	1635.00	T
FloSeal	273.00	LBS	1.7000	464.10	T
Handling	636.00	SKS	1.6000	1017.60	E
Mileage	60.00	MILE	38.1600	2289.60	E
636 sks @.06 per sk per mi					
Prod. String	1.00	JOB	785.0000	785.00	E
Head Rental	1.00	PER	75.0000	75.00	E

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 1106.23
ONLY if paid within 30 days from Invoice Date

Subtotal: 11062.30
Tax.....: 434.40
Payments: 0.00
Total....: 11496.70

8200-118
Adam D. Blue
2nd stage

RECEIVED
MAR 20 2006
KCC WICHITA

ALLIED CEMENTING CO., INC. 13589

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT:

MAR 16 2006

OAKLEY

DATE <u>1-5-06</u>	SEC <u>4</u>	TWP <u>19S</u>	RANGE <u>31W</u>	CALLED OUT <u>KCC</u>	ON LOCATION <u>10:15 AM</u>	JOB START <u>8:15 PM</u>	JOB FINISH <u>9:45 PM</u>
LEASE <u>PFEFFERT</u>	WELL # <u>4-14-1931</u>	LOCATION <u>SCOTT CITY 8E-4 1/2 S-1/2 E-3/4 N</u>			COUNTY <u>SCOTT</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>EXCELL DRILL. REG # 3</u>	OWNER <u>SAME</u>
TYPE OF JOB <u>Production str</u>	
HOLE SIZE <u>7 1/8"</u>	T.D. <u>4750'</u>
CASING SIZE <u>5 1/2"</u>	DEPTH <u>4747.69'</u>
TUBING SIZE _____	DEPTH _____
DRILL PIPE _____	DEPTH _____
TOOL <u>D-V Tool</u>	DEPTH <u>3032.84</u>
PRES. MAX _____	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	
PERFS. _____	
DISPLACEMENT <u>72 BBL WATER</u>	
EQUIPMENT	
PUMP TRUCK # <u>191</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE MAX</u>
BULK TRUCK # <u>218</u>	DRIVER <u>JACK</u>
BULK TRUCK # <u>386</u>	DRIVER <u>LARRY</u>
	CEMENT <u>545 SKS LITE 5# GILSONITE 1/2# FLO SEAL</u>
	AMOUNT ORDERED _____
	COMMON _____ @ _____
	POZMIX _____ @ _____
	GEL _____ @ _____
	CHLORIDE _____ @ _____
	<u>LITE 545 SKS @ 8.80 = 4796.40</u>
	<u>GILSONITE 2725 # @ 0.60 = 1635.00</u>
	<u>FLO-SEAL 273 # @ 1.70 = 464.10</u>
	HANDLING <u>636 SKS @ 1.60 = 1017.60</u>
	MILEAGE <u>664 PER SK/MILE = 2289.60</u>
	TOTAL <u>10202.30</u>

REMARKS:

SERVICE

MEX 15 SKS RAT HOLE, MEX 10 SKS
MOUSE HOLE, MEX 520 SKS LITE
5# GILSONITE 1/2# FLO-SEAL, WASH
TRUCK + LEASES, DISPLACE 72 BBL
WATER, Plug Landed AT 1800
PSE, D-V Tool HELD,
CEMENT did circulate

DEPTH OF JOB <u>3032.84'</u>	
PUMP TRUCK CHARGE _____	<u>785.00</u>
EXTRA FOOTAGE _____ @ _____	
MILEAGE <u>60 mi</u> @ _____	<u>N/C</u>
PLUG _____ @ _____	
<u>HEAD RENTAL</u> @ _____	<u>75.00</u>
<u>RECEIVED</u> @ _____	
<u>MAR 20 2006</u>	
TOTAL _____	<u>860.00</u>

CHARGE TO: F.F.M.L. NATURAL RESOURCES LLC.


KCC WICHITA

STREET _____
CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____



TAX _____	
TOTAL CHARGE _____	
DISCOUNT _____	IF PAID IN 30 DAYS
PRINTED NAME _____	