

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

CONFIDENTIAL
ORIGINAL

Operator: License # 32309
Name: Presco Western, LLC
Address: 5480 Valmont Rd., Ste. 350
City/State/Zip: Boulder, CO 80301
Purchaser: Plains/OneOK
Operator Contact Person: Sherry Glass
Phone: (303) 444-8881
Contractor: Name: Cheyenne
License: 33375
Wellsite Geologist: Wray Valentine

KCC
DEC 09 2005
CONFIDENTIAL

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

10-25-05	11-1-05	11-19-05
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 081-21626-0000

County: Haskell
SW NE SE NE
SE SW NE Sec. 30 Twp. 30 S. R. 33 East West

1660 feet from S (N) (circle one) Line of Section
600 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW

Lease Name: Stalker Etal Well #: 32-H30-30-33

Field Name: Victory

Producing Formation: St. Louis

Elevation: Ground: 2954.4 Kelly Bushing: 2965.4

Total Depth: 5668 Plug Back Total Depth: _____

Amount of Surface Pipe Set and Cemented at 1675 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit) ALT I Water
5-9-07

Chloride content 5000 ppm Fluid volume 1800 bbls

Dewatering method used Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: RECEIVED License No.: _____

Quarter DEC 12 2005 S. R. East West

County: KCC WICHITA Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature: Richard McClun

Title: COO Date: 12-2-05

Subscribed and sworn to before me this 9th day of December,
20 05.

Notary Public: Sherry E. Glass

Date Commission Expires: 10-8-06



KCC Office Use ONLY
YES Letter of Confidentiality Received
If Denied, Yes Date: _____
____ Wireline Log Received
____ Geologist Report Received
____ UIC Distribution

X

CONFIDENTIAL

Side Two

ORIGINAL

Operator Name: Presco Western, LLC Lease Name: Stalker Etal Well #: 32-H30-30-33
Sec. 30 Twp. 30 S. R. 33 East West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run (Submit Copy)
List All E. Logs Run:
Formation (Top), Depth and Datum
Name: St. Louis Top: 5500 Datum:
KCC DEC 09 2005 CONFIDENTIAL

CASING RECORD Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Includes rows for Surface and Production.

ADDITIONAL CEMENTING / SQUEEZE RECORD Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD - Bridge Plugs Set/Type Table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Includes a RECEIVED stamp dated DEC 12 2005 from KCC WICHITA.

TUBING RECORD Table with columns: Size, Set At, Packer At, Liner Run (Yes/No), Date of First, Resumerd Production, SWD or Enhr., Producing Method (Flowing/Pumping/Gas Lift/Other), Estimated Production Per 24 Hours (Oil Bbls., Gas Mcf, Water Bbls., Gas-Oil Ratio, Gravity).

Disposition of Gas and METHOD OF COMPLETION section with checkboxes for Vented, Sold, Used on Lease, Open Hole, Perf., Dually Comp., Commingled, and Other (Specify).

Mud-Co / Service Mud Inc.

CONFIDENTIAL

COPY

Operator Presco Western County Haskell State Kansas Pump 5 1/2 X 16 X 62 SPM Casing Program 8 5/8 @ 1675 ft.
 Well 31-H Stalker Etal Location _____ GPM 8 BPM _____ @ _____ ft.
 Contractor Cheyenne #1 Sec 30 TWP 30S RNG 33W D.P. 4 1/2 in. 197 FT/MIN R.A. _____ @ _____ ft.
 Stockpoint Pratt, KS Date 10/25/2005 Engineer Tony Maestas Collar 6 1/4 in. 641 ft. 358 FT/MIN R.A. Total Depth 5665 ft.

DATE	DEPTH feet	WEIGHT lb/gal	VISCOSITY			GELS 10 sec / 10 min.	pH Strip _ Meter _	FILTRATION/FILTRATION ANALYSIS					SAND %	RETORT			L.C.M.	Pump Press. PSI	CUMULATIVE COST	REMARKS AND TREATMENT
			Sec API @ _ F	PV @ _ F	Yp			ml API	Cake 32nds	Pres. #/BBL	Cl ppm	Ca ppm		Solids %	Oil %	Water %				
10/25	0																		0	Rig up.
10/26	1087	9.8	32	4	8	4/14	7.0	nc				200	280	7	10.6		82.4	1	1,422	Drig surface.
10/28	2681	9.7	30	3	6	2/4	7.0	nc				20m	Hvy		8.8		91.2		2,573	Drig.
10/29	2861	8.5	59	16	12		7.0	13.6	2			2,500	180	2	5.0		93.0	12	6,629	CCM
10/30	3731	9.3	42	7	19	19/28	7.0	52.0	8			4,000	1,000		6.9		93.1	8	7,897	Drig.
10/31	4749	9.2	48	15	10	12/33	7.5	11.2	1			1,800	160		6.3		93.7	9	12,241	Drig.
11/1	5313	9.4	43	13	16	12/35	11.0	8.8	1			1,500	40		7.7		92.3	6	14,033	Drig.
11/2	5640	9.2	55	14	21	12/44	10.5	7.2	1			1,900	40		6.2		93.8	5	16,800	Drig.
11/3	5665																		16,914	Final: RTD - 5668'. LTD - 5665'. Run casing.
Reserve Pit: 5000 ppm. Chloride 1800 bbls. Volume																				

RECEIVED
DEC 17 2005
KCC WICHITA

		Materials		Sacks	Amount	Materials		Sacks	Amount			Amount	
MUD-CO / SERVICE MUD INC. 100 S. Main Suite #310 Wichita, Ks. 67202 316/264-2814 Fax: 316/264-5024 DRILLING MUD RECAP		C/S HULLS		620	7,285.00								
		CAUSTIC SODA		26	1,313.26								
		DRILL PAK		4	1,220.00								
		LIME		12	99.00								
		PREMIUM GEL		608	6,232.00							Total Mud Cost	16,914.16
		SODA ASH 50#		29	553.90							Trucking Cost	3,284.11
		SUPER LIG		10	211.00							Trucking Surcharge	492.62
										Taxes			
										TOTAL COST		20,690.89	

ALLIED CEMENTING CO., INC.

21654

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT:

OAKLEY

DATE <u>10-26-05</u>	SEC. <u>30</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>5:45 PM</u>	JOB START <u>1:15 AM</u>	JOB FINISH <u>2:30 AM</u>
LEASE <u>STAKER ETAL</u>	WELL # <u>1130</u>	LOCATION <u>SATANTA 1/2S-1E-1/2S-W INTD</u>			COUNTY <u>HASKELL</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR CHEYENNE DRILL RIG #1

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4" T.D. 1675'

CASING SIZE 8 3/8" DEPTH 1675'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 40.47'

CEMENT LEFT IN CSG. 40.47'

PERFS.

DISPLACEMENT 104 BBL

OWNER SAME

CEMENT

AMOUNT ORDERED 150 SKS COM 3%CC
575 SKS LITE 3%CC 1/4" FLO-SEAL

COMMON	<u>150 SKS</u>	@	<u>10⁰⁰</u>	<u>1500⁰⁰</u>
POZMIX		@		
GEL		@		
CHLORIDE	<u>24 SKS</u>	@	<u>38⁰⁰</u>	<u>912⁰⁰</u>
ASC		@		
LITE	<u>575 SKS</u>	@	<u>9³⁰</u>	<u>5347⁵⁰</u>
FLO-SEAL	<u>144⁰⁰</u>	@	<u>1⁷⁰</u>	<u>244⁸⁰</u>
HANDLING	<u>778 SKS</u>	@	<u>1⁶⁰</u>	<u>1244⁸⁰</u>
MILEAGE	<u>64 PER SK/ MILE</u>			<u>1460⁴⁰</u>
TOTAL				<u>10,649⁵⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

191 HELPER WAYNE MAX

BULK TRUCK

394 DRIVER MIKE

BULK TRUCK

347 DRIVER ALAN

REMARKS:

MIX 575 SKS LITE 3%CC 1/4" FLO-SEAL
150 SKS COM 3%CC + DISPLACE 104 BBL
WATER:

CEMENT CTRD CTRL
PLUG LANDED AT 1000 PSI
FLOAT DIDN'T HOLD

THANK YOU

CHARGE TO: PRESCO-WESTERN

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>1675'</u>		
PUMP TRUCK CHARGE			<u>1320⁰⁰</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30 ME</u>	@	<u>5⁰⁰</u> <u>150⁰⁰</u>
MANIFOLD		@	
		@	
		@	
TOTAL <u>1470⁰⁰</u>			

RECEIVED

DEC 12 2005

KCC WICHITA

8 3/8 PLUG & FLOAT EQUIPMENT

1- GUIDE SHOE			<u>235⁰⁰</u>
1- AFU INSERT	@		<u>325⁰⁰</u>
4- CENTRALIZERS	@	<u>55⁰⁰</u>	<u>220⁰⁰</u>
1- BASKET	@		<u>180⁰⁰</u>
1- RUBBER PLUG	@		<u>100⁰⁰</u>
TOTAL <u>1060⁰⁰</u>			

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzalez

Rodney Gonzalez
PRINTED NAME

ALLIED CEMENTING CO., INC.

21678

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL SERVICE POINT:
Oakley

DATE <i>11-3-05</i>	SEC <i>30</i>	TWP. <i>30s</i>	RANGE <i>33w</i>	CALLED OUT	ON LOCATION <i>7:30 AM</i>	JOB START <i>4:15 PM</i>	JOB FINISH <i>5:15 PM</i>
LEASE <i>Stalker</i>	WELL# <i>H-30</i>	LOCATION <i>Satanta 1 3/4 S 1 E 1/2 S W/5</i>		COUNTY <i>Osage</i>	STATE <i>KS</i>		
OLD OR <u>NEW</u> (Circle one)							

COPY

CONTRACTOR <i>Cheyenne Drlg Rig 1</i>	OWNER <i>Same</i>
TYPE OF JOB <i>Production string</i>	
HOLE SIZE <i>7 1/4</i>	T.D. <i>5668'</i>
CASING SIZE <i>5 1/2</i>	DEPTH <i>5668'</i>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <i>Port collar</i>	DEPTH <i>3062'</i>
PRES. MAX <i>1800#</i>	MINIMUM
MEAS. LINE	SHOE JOINT <i>26.75'</i>
CEMENT LEFT IN CSG. <i>26.75'</i>	
PERFS.	
DISPLACEMENT <i>134 1/4 Bbls</i>	
EQUIPMENT	

CEMENT			
AMOUNT ORDERED	<i>300 sks ASC, 27 gal</i>		
	<i>10 gal Salt, 5 gal Sk. Gilsonite, 5 gal PL</i>		
	<i>PL 160</i>	<i>50 gals WFR-2</i>	
COMMON		@	
POZMIX		@	
GEL	<i>6 sks</i>	@ <i>14.00</i>	<i>84.00</i>
CHLORIDE		@	
ASC	<i>300 sks</i>	@ <i>11.65</i>	<i>3495.00</i>
PL 160	<i>141#</i>	@ <i>8.75</i>	<i>1226.70</i>
		@ <i>8.70</i>	
Salt	<i>31 sks</i>	@ <i>15.75</i>	<i>498.25</i>
Gilsonite	<i>1500#</i>	@ <i>.60</i>	<i>900.00</i>
		@	
		@	
500 gals WFR-2		@ <i>1.00</i>	<i>500.00</i>
		@	
HANDLING	<i>387 sks</i>	@ <i>1.60</i>	<i>619.20</i>
MILEAGE	<i>64 / sk mile</i>		<i>696.60</i>
			TOTAL <i>8009.75</i>

PUMP TRUCK	CEMENTER <i>Dean</i>
# <i>373-281</i>	HELPER <i>Andrew</i>
BULK TRUCK	
# <i>394</i>	DRIVER <i>Kelly</i>
BULK TRUCK	
#	DRIVER

REMARKS:

*Pump 500 gals WFR-2 down to CSG.
Plug mouse hole w/ 10 sks
Plug Rat Hole w/ 15 sks
Mix 27.5 sks cement down 5 1/2 csg.
Wash pump & line. Release plug & plug
134 1/2 Bbls water. Plug landed lift plug
1400#, Land Plug 1800#. Plant Hole
Thank you*

SERVICE

DEPTH OF JOB	<i>5668'</i>		
PUMP TRUCK CHARGE			<i>1570.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>30 miles</i>	@ <i>5.00</i>	<i>150.00</i>
MANIFOLD		@	
Head Rental		@	<i>75.00</i>
		@	
			TOTAL <i>1735.00</i>
			TOTAL <i>1660.00</i>

CHARGE TO: *Presto western*
STREET _____
CITY _____ STATE _____ ZIP _____

RECEIVED

DEC 12 2005

To Allied Cementing Co., Inc. **KCC WICHITA**
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

Guide shoe			<i>160.00</i>
APU Insert	@		<i>235.00</i>
2-Centrizers	@ <i>50.00</i>		<i>350.00</i>
1-Basket	@		<i>140.00</i>
1-Port Collar	@		<i>1750.00</i>
5/2 Rubber Plug	@		<i>60.00</i>
			TOTAL <i>2695.00</i>

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *Rodney Gonzales*

Rodney Gonzales
PRINTED NAME