

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 33074
Name: Dart Cherokee Basin Operating Co., LLC
Address: P O Box 177
City/State/Zip: Mason MI 48854-0177
Purchaser: Oneok
Operator Contact Person: Beth Oswald
Phone: (517) 244-8716
Contractor: Name: McPherson
License: 5675
Wellsite Geologist: Bill Barks
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date
<u>8-11-05</u>	<u>8-15-05</u>	<u>9-13-05</u>

API No. 15 - 125-30822-00-00
County: Montgomery
SE Sec. 3 Twp. 33 S. R. 15 East West
350' FSL feet from S / N (circle one) Line of Section
2900' FEL feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Medsker Well #: D2-3
Field Name: Cherokee Basin Coal Gas Area
Producing Formation: Penn Coals
Elevation: Ground: 780' Kelly Bushing: _____
Total Depth: 1364' Plug Back Total Depth: 1354'
Amount of Surface Pipe Set and Cemented at 43 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan ALT #2 KJR 5/18/07
(Data must be collected from the Reserve Pit)
Chloride content NA ppm Fluid volume 260 bbls
Dewatering method used empty w/ vac trk and air dry
Location of fluid disposal if hauled offsite: _____
Operator Name: Dart Cherokee Basin Operating Co LLC
Lease Name: Butler A1-26 SWD License No.: 33074
Quarter NW Sec. 26 Twp. 33 S. R. 14 East West
County: Montgomery Docket No.: D-27878

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Beth Oswald
Title: Admn Engr Asst Date: 12-1-05
Subscribed and sworn to before me this 13th day of December,
2005
Notary Public: Karen L. Welton
Date Commission Expires: _____

KAREN L. WELTON
Notary Public - Michigan
Ingham County
My Commission Expires Mar 3, 2007
Acting in the County of Ingham

KCC Office Use ONLY
ND Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: Medsker Well #: D2-3
 Sec. 3 Twp. 33 S. R. 15 ✓ East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes ✓ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes ✓ No

Cores Taken Yes ✓ No

Electric Log Run ✓ Yes No
 (Submit Copy)

List All E. Logs Run:

High Resolution Compensated Density Neutron & Dual Induction

Log Formation (Top), Depth and Datum ✓ Sample
 Name Top Datum
 See Attached

RECEIVED
 DEC 05 2005
 KCC WICHITA

CASING RECORD							
				New	Used		
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	11"	8 5/8"	24#	43'	Class A	8	
Prod	6 3/4"	4 1/2"	10.5#	1361'	Thick Set	140	See Attached

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	1194.5'-1196'	300 gal 15% HCl, 2310# sd, 225 BBL fl	
4	1147'-1148'	300 gal 15% HCl, 1705# sd, 200 BBL fl	
4	958.5'-961.5'	300 gal 15% HCl, 20 bio-balls, 4505# sd, 325 BBL fl	
4	881'-882.5'	300 gal 15% HCl, 850# sd, 165 BBL fl	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2 3/8"	1326'	NA	Yes <input checked="" type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr.	Producing Method
11-5-05	Flowing <input type="checkbox"/> Pumping <input checked="" type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) <input type="checkbox"/>

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	NA	0	10	NA	NA

Disposition of Gas METHOD OF COMPLETION Production Interval

Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled
 (If vented, Sumit ACO-18.) Other (Specify) _____

CONSOLIDATED OIL WELL SERVICES, INC.
 211 W. 14TH STREET, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

TICKET NUMBER 5180
 LOCATION EUREKA
 FOREMAN Kevin McCoy

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
8-16-05	2368	Medsker D2-3				MB	
CUSTOMER <u>Dart Cherokee Basin</u>							
MAILING ADDRESS <u>3541 Co. Rd. 5400</u>							
CITY <u>Independence</u>		STATE <u>Ks</u>	ZIP CODE <u>67301</u>	Gus Jones Rig 2			
				TRUCK #	DRIVER	TRUCK #	DRIVER
				<u>445</u>	<u>RICK</u>		
				<u>439</u>	<u>JUSTIN</u>		
				<u>437</u>	<u>LARRY</u>		

JOB TYPE Longstring HOLE SIZE 6 3/4 HOLE DEPTH 1364' CASING SIZE & WEIGHT 4 1/2 10.5* New
 CASING DEPTH 1361' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.2* SLURRY VOL 43 BBL WATER gal/sk 8.0 CEMENT LEFT in CASING 0'
 DISPLACEMENT 21.6 BBL DISPLACEMENT PSI 700 ~~MAX~~ PSI 1200 Bump Plug RATE _____

REMARKS: Safety Meeting: Rig up to 4 1/2 casing. Break circulation w/ 30 BBL fresh water. Pump 4 sks Gel flush w/ Hulls, 10 BBL foamer, 10 BBL water spacer. Mixed 140 sks Thick Set Cement w/ 8* Kol-Seal per/sk @ 13.2* per/gal yield 1.73. Wash out pump & lines. Shut down. Release Plug. Displace w/ 21.6 BBL fresh water. Final Pumping Pressure 700 PSI. Bump Plug to 1200 PSI. Wait 2 minutes. Release Pressure. Float Held. Shut casing in @ 0 PSI. Good Cement Returns to Surface = 9 BBL slurry. Job Complete. Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		
5406	36	MILEAGE	765.00	765.00
			2.50	90.00
1126 A	140 SKS	Thick Set Cement	13.00	1820.00
1110 A	22 SKS	Kol-Seal 8* per/sk	16.90	371.80
1118 A	4 SKS	Gel flush	6.63	26.52
1105	1 SK	Hulls	14.50	14.50
5407	Tons	Ton Miles Bulk Truck	MIC	240.00
4404	1	4 1/2 Top Rubber Plug RECEIVED	38.00	38.00
1238	1 gal	SOAP	32.15	32.15
1205	2 gals	Bi-Cide	24.15	48.30
5502c	4 Hrs	80 BBL VAC TRUCK KCC WICHITA	82.00	328.00
1123	3000 gals	City water	12.20 ^{per 1000}	36.60
Sub Total				3810.87
Thank you			5.3%	
SALES TAX				122.30
ESTIMATED TOTAL				3933.17

AUTHORIZATION [Signature] TITLE 199/21 DATE _____