

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

CONFIDENTIAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

KCC

Operator: License # 5316
Name: Falcon Exploration, Inc.
Address: 155 N. Market, Ste 1020
City/State/Zip: Wichita, KS 67202
Purchaser: pending
Operator Contact Person: Ron Schraeder / Mike Mitchell
Phone: (316) 262-1378
Contractor: Name: Clarke Corporation
License: 5105
Wellsite Geologist: n/a

Designate Type of Completion:
____ New Well Re-Entry ____ Workover
____ Oil ____ SWD ____ SLOW ____ Temp. Abd.
 Gas ____ ENHR ____ SIGW
____ Dry ____ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: Graves Drilling / CMX, INC.
Well Name: #2 Whelan / Whelan "OWWO" #1
Original Comp. Date: 06/17/077 Original Total Depth: 4412
____ Deepening ____ Re-perf. ____ Conv. to Enhr./SWD
____ Plug Back ____ Plug Back Total Depth
____ Commingled Docket No. ____
____ Dual Completion Docket No. ____
____ Other (SWD or Enhr.?) Docket No. ____
12/13/04 12/15/04 01/31/05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 007-20509-00-02
County: Barber
approx. E/2 SE NE Sec. 29 Twp. 31 S. R. 11 East West
3255 feet from (S) N (circle one) Line of Section
375 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Whelan Well #: #2 OWWO
Field Name: Whelan Ext.
Producing Formation: Snyderville Sand
Elevation: Ground: 1625 Kelly Bushing: 1633
Total Depth: 4420 Plug Back Total Depth: 4409
Amount of Surface Pipe Set and Cemented at 215 Feet
Multiple Stage Cementing Collar Used? Yes No
yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
ACT I OWNED WITH 4-20-07
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used trucked to disposal
Location of fluid disposal if hauled offsite:
Operator Name: Herman Loeb
Lease Name: Lomann License No.: 3273
Quarter sw Sec. 3 Twp. 35 S. R. 12 East West
County: Barber Docket No.: C-4812

RECEIVED
MAY 11 2005
KCC WICHITA

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Ronald P. Schipper
Title: Engineer Date: 05/05/05
Subscribed and sworn to before me this 10th day of May,
2005.
Notary Public: Rosann M. Schippers
Date Commission Expires: 9/28/07

KCC Office Use ONLY
____ Letter of Confidentiality Received
If Denied, Yes Date: _____
____ Wireline Log Received
____ Geologist Report Received
____ UIC Distribution

ROSANN M. SCHIPPERS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/28/07

ALLIED CEMENTING CO., INC. 20266

Federal Tax I.D.#

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

KCC SERVICE POINT:
MAY 11 2005 *Med Lodge*

DATE <u>12-15-04</u>	SEC <u>29</u>	TWP <u>31s</u>	RANGE <u>11 W</u>	CALLED OUT <u>5:00pm</u>	LOCATION <u>CONFIDENTIAL</u>	JOB START <u>4:00pm</u>	JOB FINISH <u>5:00pm</u>
LEASE <u>Wheeland</u>		WELL # <u>2</u>		LOCATION <u>160 + Label Rd</u>		COUNTY <u>Barber</u>	STATE <u>Ks</u>
OLD OR <u>NEW</u> (Circle one)		LOCATION <u>1E 4-51 W/into</u>					

CONTRACTOR Clark Corp

TYPE OF JOB Long String

HOLE SIZE 7 7/8 T.B. 4418

CASING SIZE 5 1/2 DEPTH 4418

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 1500 MINIMUM 100

MEAS. LINE SHOE JOINT 8ft

CEMENT LEFT IN CSG. 8ft

PERFS.

DISPLACEMENT 105 1/2 bbls 28 KOL water

OWNER Falcon Exp

CEMENT

AMOUNT ORDERED 175 gal Adc + 5" Kol Seal, 500 gal Mud Clean, 12 gal Cla Pro

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC	@	<u>175</u>	<u>9.80</u> <u>1715.00</u>
<u>Kol Seal</u>	@	<u>875</u>	<u>1.50</u> <u>437.50</u>
<u>Mud Clean</u>	@	<u>500 gal</u>	<u>1.00</u> <u>500.00</u>
<u>Cl Pro</u>	@	<u>12 gal</u>	<u>22.90</u> <u>274.80</u>
HANDLING	@	<u>224</u>	<u>1.35</u> <u>302.40</u>
MILEAGE	@	<u>7 x 224 x .05</u>	<u>150.00</u>
			<u>Min chrg.</u> TOTAL <u>3379.70</u>

EQUIPMENT

PUMP TRUCK # 372 CEMENTER Mark HELPER Daren

BULK TRUCK # 381 DRIVER Josh RECEIVED

BULK TRUCK # DRIVER MAY 11 2005

REMARKS:

Pipe on bottom, break circulation
pump 3 fresh 10 caustic 3 fresh
pump 175 gal cement. Shut down
Wash pump + line. Release plug
start displacement pump 105 1/2
bbls 28 KOL water bump plug at
1000 psi to 1500 float held

CHARGE TO: Falcon Exploration

STREET Box 551

CITY Russell STATE Ks ZIP _____

SERVICE

DEPTH OF JOB 4418

PUMP TRUCK CHARGE 1245.00

EXTRA FOOTAGE @ _____

MILEAGE 7 @ 4.00 28.00

MANIFOLD @ _____

TOTAL 1273.00

PLUG & FLOAT EQUIPMENT

5 1/2

<u>1-guide shoe</u>	@	<u>150.00</u>	<u>150.00</u>
<u>1-float collar AFO</u>	@	<u>235.00</u>	<u>235.00</u>
<u>5 Turboplayers</u>	@	<u>60.00</u>	<u>300.00</u>
<u>2 Baskets</u>	@	<u>128.00</u>	<u>256.00</u>
<u>12-Recip Scratchers</u>	@	<u>35.00</u>	<u>420.00</u>
<u>8ft landing joint</u>	@	<u>9.00</u>	<u>72.00</u>
<u>1-Rubber Plug</u>	@	<u>60.00</u>	<u>60.00</u>
			TOTAL <u>1493.00</u>

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE ~~3379.70~~

DISCOUNT ~~_____~~ IF PAID IN 30 DAYS

SIGNATURE *Mark Kuhn* ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

PRINTED NAME Mark Kuhn