

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

CONFIDENTIAL

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 33351
Name: BuRay, LLC
Address: 2425 Hwy 41 N, Suite 130
City/State/Zip: Evansville, IN 47711
Purchaser: Clear Creek
Operator Contact Person: Earl Ochanpaugh
Phone: (620) 272-1219
Contractor: Name: Cheyenne Drilling, LLP
License: 33375
Wellsite Geologist: Barry Mercer

RECEIVED
APR 11 2005
KCC WICHITA
KCC
MAR 10 2005

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

CONFIDENTIAL

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>1/11/2005</u>	<u>1/16/2005</u>	
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 055-21860-00-00
County: Finney
W1/2 - NE1/4 - SE1/4 - _____ Sec. 5 Twp. 23 S. R. 31 East West
1,980 feet from (S) N (circle one) Line of Section
990 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Becker Well #: 5-5
Field Name: Stewart

Producing Formation: Morrow Sand
Elevation: Ground: 2,879.5' Kelly Bushing: 2885'
Total Depth: 4972 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 458 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 1700'
feet depth to Surface w/ 400 _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit) ALT II WFW
4-4-07
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____

Location of fluid disposal if hauled offsite:
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: mgr Date: 3-18-05
Subscribed and sworn to before me this 18 day of March
20 05
Notary Public: [Signature]
Date Commission Expires: 10-25-08

KCC Office Use ONLY
yes Letter of Confidentiality Received
If Denied, Yes Date: _____
_____ Wireline Log Received
_____ Geologist Report Received
_____ UIC Distribution

✓

X

CONFIDENTIAL

Side Two

ORIGINAL

Operator Name: BuRay, LLC Lease Name: Becker Well #: 5-5
Sec. 5 Twp. 23 S. R. 31 County: Finney

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken [] Yes [x] No
Samples Sent to Geological Survey [] Yes [x] No
Cores Taken [] Yes [x] No
Electric Log Run [x] Yes [] No
List All E. Logs Run:

[x] Log Formation (Top), Depth and Datum [] Sample
Name KCC Top Datum 2880'
Kriider MAR 10 2005 2,270' (+210)
Lansing 4,048' (-1,168)
B/KC 4,480' (-1,600)
Morrow 4,730' (-1,850)
Mississippian 4.817' (-1,937)
St. Louis 4,900' (-2,020)

DIL/MEL RECEIVED
CNL/CDL APR 11 2005

Table with 8 columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Row 1: 4899.37, 7 7/8, 4 1/2, 10.5, 4899.37, "C", 225.

ADDITIONAL CEMENTING / SQUEEZE RECORD
Table with 5 columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Row 1: Protect Casing, 1700, Lite, 400, Flo-Seal 100#

PERFORATION RECORD - Bridge Plugs Set/Type
Table with 4 columns: Shots Per Foot, PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Row 1: 4, 4880' - 4900' 20', NONE

TUBING RECORD
Table with 4 columns: Size, Set At, Packer At, Liner Run. Row 1: 2 3/8, 4880, NONE, [] Yes [x] No
Date of First, Resumerd Production, SWD or Enhr. Producing Method [] Flowing [x] Pumping [] Gas Lift [] Other (Explain)
Estimated Production Per 24 Hours Oil Bbls. Gas Mcf Water Bbls. Gas-Oil Ratio Gravity. Row 1: 5, 5

Disposition of Gas METHOD OF COMPLETION Production Interval
[] Vented [] Sold [x] Used on Lease [] Open Hole [x] Perf. [] Dually Comp. [] Commingled
(if vented, Submit ACO-18.) [] Other (Specify)

CONFIDENTIAL ORIGINAL
ALLIED CEMENTING CO., INC. 19888

TO P.O. BOX 31
 RUSSELL, KANSAS 67665

TOP STAGE

MAR 10 2005

SERVICE POINT:

CONFIDENTIAL

oakley

DATE <i>1-16-05</i>	SEC. <i>5</i>	TWP. <i>23s</i>	RANGE <i>3/W</i>	CALLED OUT	ON LOCATION	JOB START <i>1:00 PM</i>	JOB FINISH <i>1:45 PM</i>
LEASE <i>Becker</i>	WELL # <i>5-5</i>	LOCATION <i>Garden City N to 6 mile Rd</i>		COUNTY <i>Linney</i>	STATE <i>Ks</i>		
OLD OR <input checked="" type="radio"/> NEW (Circle one)				<i>7E 1N 3/4E 1/2 N W1S</i>		RECEIVED	

CONTRACTOR *Cheyenne Drilling Rig II*

TYPE OF JOB *Two Stage (TOP)*

HOLE SIZE *7 7/8* T.D. *4960'*

CASING SIZE *4 1/2* DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL *DV 7001* DEPTH *1700'*

PRES. MAX *1500 #* MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

OWNER *Same*

APR 11 2005

KCC WICHITA

DISPLACEMENT *27 Bbls*

EQUIPMENT

PUMP TRUCK CEMENTER *Dean*

373-281 HELPER *Andrew*

BULK TRUCK

386 DRIVER *Larry*

BULK TRUCK

218 DRIVER *Honnie*

315 *Alan*

CEMENT	AMOUNT ORDERED		
	<i>450 sks Lite 1/4 # Flo Seal</i>		
	<i>Used 400 sks</i>		
COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC	@		
<i>Lite weight 400 sks</i>	@ <i>7.95</i>	<i>3180.00</i>	
<i>Flo Seal 100 #</i>	@ <i>1.40</i>	<i>140.00</i>	
HANDLING <i>450 sks</i>	@ <i>1.35</i>	<i>607.50</i>	
MILEAGE <i>54 / sk/mile</i>		<i>1462.50</i>	
TOTAL		<i>5390.00</i>	

REMARKS:

*Drop Dart waited 10 min. upon
 Tool Had circulation. Mix
 400sk Lite 1/4 Flo Seal.
 Cement circulated to Pit.
 Wash Pump & Line & Disp 27 Bbls
 Lost circulation. Lift press was
 500. Plug landed & Tool closed
 1500 # Post Held.
 witness Dean Runday Thank you
 Walt Dell*

SERVICE

DEPTH OF JOB	<i>1700'</i>		
PUMP TRUCK CHARGE		<i>700.00</i>	
EXTRA FOOTAGE	@		
MILEAGE <i>6.5 miles</i>	@	<i>N/C</i>	
MANIFOLD	@		
<i>Waiting Time 8hrs</i>	@ <i>125.00</i>	<i>1000.00</i>	

CHARGE TO: *Schofield Energy / BuRay Energy*

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL *1700.00*

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE

[Signature]

Schofield Energy / BuRay
 PRINTED NAME

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ALLIED CEMENTING CO. INC. 19889

CONFIDENTIAL **ORIGINAL**

TO P.O. BOX 31
RUSSELL, KANSAS 67665

MAR 10 2005

SERVICE POINT:

Bottom Stage
CONFIDENTIAL *Oakley*

DATE <i>7-16-05</i>	SEC. <i>5</i>	TWP <i>23s</i>	RANGE <i>3W</i>	CALLED OUT	ON LOCATION <i>6:45 PM</i>	JOB START <i>12:45 PM</i>	JOB FINISH <i>12:50 PM</i>
LEASE <i>Becker</i>	WELL # <i>5-5</i>	LOCATION <i>Garden City N to 6 mile Rd</i>			COUNTY <i>Finnay</i>	STATE <i>KS</i>	
OLD OR <u>NEW</u> (Circle one)				<i>7E 1N 4E 1/2 N W/4</i>			

RECEIVED
APR 11 2005

CONTRACTOR *Cheyenne Drlg Rig 11*

TYPE OF JOB *Two Stage (Bottom)*

HOLE SIZE *7 1/8* T.D. *4960'*

CASING SIZE *4 1/2* DEPTH *4899.37'*

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL *DV 7001* DEPTH *1700'*

PRES. MAX *1000#* MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT *50 Bbls Water + 28 Bbls Mud*

OWNER *same*

CEMENT AMOUNT ORDERED *225 SKs Class "C"*

<i>class "C"</i>			
COMMON	<i>225 SKs</i>	<i>@ 10.95</i>	<i>2463.75</i>
POZMIX		@	
GEL		@	
CHLORIDE		@	
ASC		@	
<i>Lifeweight</i>		@ <i>7.95</i>	
<i>Float</i>		@ <i>1.40</i>	
<i>WFR-2 500 gals</i>		@ <i>1.00</i>	<i>500.00</i>
HANDLING	<i>225.0 SKs</i>	@ <i>1.35</i>	<i>303.75</i>
MILEAGE	<i>54/sk/mile</i>		<i>731.25</i>
TOTAL			<i>3998.75</i>

EQUIPMENT

PUMP TRUCK CEMENTER *Dean*

373-281 HELPER *Andrew*

BULK TRUCK

386 DRIVER *Larry*

BULK TRUCK

218 DRIVER *Lonnie*

315 *Ahan*

REMARKS:

pump 500 gals WFR-2 followed w/ 225 SKs class "C", wash pump & line, Disp w/ 50 Bbls water & 28 Bbls Mud. Lift press 500# Plug landed at 1000#.

Float Held.

Thank you

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ *1180.00*

EXTRA FOOTAGE @ _____

MILEAGE *65 miles* @ *4.00* *260.00*

MANIFOLD @ _____

TOTAL *1440.00*

CHARGE TO: *Schofield Energy / BuRay Energy*

STREET *2425 Highway 41N suite 130*

CITY *Evanville* STATE *IN* ZIP *47711*

PLUG & FLOAT EQUIPMENT

<i>Float shoe</i>	@	<i>200.00</i>
<i>10 - centralizers</i>	@ <i>45.00</i>	<i>450.00</i>
<i>2 - Basket</i>	@ <i>116.00</i>	<i>232.00</i>
<i>1 - DV Tool</i>	@	<i>3000.00</i>
TOTAL <i>3882.00</i>		

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *[Signature]*

Schofield Energy / BuRay
PRINTED NAME *ccs*

CONFIDENTIAL

ALLIED CEMENTING CO., INC.

ORIGINAL 19486

REMIT TO P.O. BOX 31 RUSSELL, KANSAS 67665

Surface Job

MAR 10 2005 SERVICE POINT:

Oakley

CONFIDENTIAL

DATE	1-11-05	SEC.	5	TWP.	23 ^S	RANGE	31 ^W	CALLED OUT		ON LOCATION	10:00 PM	JOB START	Midnite	JOB FINISH	12:15 AM
LEASE	Becker	WELL #	5-5	LOCATION	Garden City North to 6-milard			COUNTY	Finnney	STATE	Kan				
OLD OR NEW	(Circle one)														

RECEIVED

APR 11 2005

KCC WICHITA

CONTRACTOR	Cheyenne Drly Co #11		OWNER	Same	
TYPE OF JOB	Surface		CEMENT		
HOLE SIZE	12 1/4	T.D.	458'	AMOUNT ORDERED	275 SKS COM
CASING SIZE	8 7/8	DEPTH	457'	3% CC - 2% Gel	
TUBING SIZE		DEPTH			
DRILL PIPE		DEPTH			
TOOL		DEPTH			
PRES. MAX		MINIMUM			
MEAS. LINE		SHOE JOINT			
CEMENT LEFT IN CSG.	15'				
PERFS.					
DISPLACEMENT	28 1/2 BBL				

EQUIPMENT

PUMP TRUCK	CEMENTER	Walt
# 373	HELPER	Andrew
BULK TRUCK		
# 218	DRIVER	Larry
BULK TRUCK		
#	DRIVER	

REMARKS:

Cement Did Circ

Thank You

CHARGE TO: Buray, LLC
 STREET 300 Kings Valley
 CITY Evansville STATE Indiana ZIP 47211

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Noel Perez

COMMON	275 SKS @ 9.10	2,502.50
POZMIX	@	
GEL	5 SKS @ 11.00	55.00
CHLORIDE	9 SKS @ 33.00	297.00
ASC	@	
HANDLING	289 SKS @ 1.35	390.15
MILEAGE	54 per SK mile	939.25
TOTAL		4,183.90

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		570.00
EXTRA FOOTAGE	@	
MILEAGE	65 miles @ 4.00	260.00
MANIFOLD	@	
TOTAL		830.00

PLUG & FLOAT EQUIPMENT

8 5/8		
1- Centralizer	@	55.00
	@	
	@	
	@	
	@	
TOTAL		55.00

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

Noel Perez

PRINTED NAME