

RECEIVED

AUG 3 2005

KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

CONFIDENTIAL

Operator: License # 5144  
Name: Mull Drilling Company, Inc.  
Address: P.O. Box 2758  
City/State/Zip: Wichita KS 67201-2758  
Purchaser: STG  
Operator Contact Person: Mark Shreve  
Phone: (316) 264-6366  
Contractor: Name: Duke Drilling Company, Inc.  
License: 5929

KCC  
AUG 03 2005

CONFIDENTIAL

Wellsite Geologist: Kevin Kessler  
Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled Docket No. \_\_\_\_\_  
 Dual Completion Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?) Docket No. \_\_\_\_\_

6/6/05	6/19/05	7/1/05
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 101-21881 - 00-00  
County: Lane  
S/2 - S/2 - NW Sec. 28 Twp. 17s S. R. 28  East  West  
2280 feet from S (N circle one) Line of Section  
1310 feet from E (W circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE (NW) SW  
Lease Name: Reifschneider Well #: 1-28  
Field Name: Wildcat


Producing Formation: Marmaton  
Elevation: Ground: 2709' Kelly Bushing: 2718'  
Total Depth: 4580' Plug Back Total Depth: 4539'  
Amount of Surface Pipe Set and Cemented at 208' Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set 2076' Feet  
If Alternate II completion, cement circulated from 2076'  
feet depth to surface w/ 230 sx cmt.

Drilling Fluid Management Plan *ACT II WITH*  
(Data must be collected from the Reserve Pit) *4-23-07*  
Chloride content 41,000 ppm Fluid volume 800 bbis  
Dewatering method used evaporation  
Location of fluid disposal if hauled offsite:  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: \_\_\_\_\_  
Title: President/COO Date: 8/3/05  
Subscribed and sworn to before me this 3rd day of August 05.  
Notary Public: *Tannis L. Tritt*  
Date Commission Expires: 3-26-07



**KCC Office Use ONLY**  
*YES* Letter of Confidentiality Attached  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

CONFIDENTIAL

Side Two

ORIGINAL

Operator Name: Mull Drilling Company, Inc. Lease Name: Reifschneider Well #: 1-28
Sec. 28 Twp. 17s S. R. 28 East West County: Lane

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken [X] Yes [ ] No
Samples Sent to Geological Survey [X] Yes [ ] No
Cores Taken [ ] Yes [X] No
Electric Log Run [X] Yes [ ] No
List All E. Logs Run:

ELI: CDL/CNL/PE; DIL; Micro & Sonic

Table with 3 columns: Name, Top, Datum. Rows include Anhydrite, B/Anhydrite, Lansing, B/KC, and Mississippian with corresponding depth values.

CASING RECORD [X] New [ ] Used

Report all strings set-conductor, surface, intermediate, production, etc.

Table with 8 columns: Purpose of String, Size Hole Drilled, Size Casing Set (in O.D.), Weight Lbs./ Ft., Setting Depth, Type of Cement, # Sacjs Used, Type and Percent Additives. Rows for Surface and Production.

ADDITIONAL CEMENTING / SQUEEZE RECORD

Table with 5 columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Includes a RECEIVED stamp dated AUG 05 2005 and KCC WICHITA.

Table with 3 columns: Shots Per Foot, PERFORATION RECORD - Bridge Plugs Set/Type, Acid, Fracture, Shot, Cement Squeeze Record. Includes handwritten values for perforation intervals.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run. Values: 2 3/8", 4516', [ ] Yes [X] No.

Table with 2 columns: Date of First, Resumerd Production, SWD or Enhr. (7/1/05), Producing Method ([ ] Flowing [X] Pumping [ ] Gas Lift [ ] Other).

Table with 5 columns: Estimated Production Per 24 Hours (Oil Bbls. 110, Gas Mcf 0, Water Bbls. 0, Gas-Oil Ratio N/A, Gravity 35.5).

Disposition of Gas METHOD OF COMPLETION Production Interval
[ ] Vented [ ] Sold [ ] Used on Lease [ ] Open Hole [ ] Perf. [ ] Dually Comp. [ ] Commingled
[ ] Other (Specify)

# ALLIED CEMENTING CO., INC.

17979

**CONFIDENTIAL**

**KCC**

**ORIGINAL**

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

AUG 03 2005

SERVICE POINT:

*Mass City*

**CONFIDENTIAL**

DATE <i>6-6-05</i>	SEC. <i>7</i>	TWP. <i>18</i>	RANGE <i>22w</i>	CALLED OUT <i>9:00 am</i>	ON LOCATION <i>12:30 pm</i>	JOB START <i>3:00 pm</i>	JOB FINISH <i>4:00 pm</i>
LEASE <i>1712 E. Meiden</i>	WELL # <i>129</i>	LOCATION <i>Dighton - 3000th - 22</i>	COUNTY <i>Osage</i>	STATE <i>KS</i>	HOME		
OLD OR <input checked="" type="radio"/> NEW (Circle one)		<i>East - North - East into</i>					

CONTRACTOR *Dube #4*

TYPE OF JOB *Surface pipe*

HOLE SIZE *12 1/4* TD. *209'*

CASING SIZE *8 5/8* DEPTH *208'*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. *approx 15'*

PERFS.

DISPLACEMENT *13 BBLS*

OWNER *Mull Oalg co.*

CEMENT

AMOUNT ORDERED *125 sy Common*

*3% gel*

COMMON	<i>155 ul</i>	@	<i>8.70</i>	<i>1348.50</i>
POZMIX		@		
GEL	<i>3 ul</i>	@	<i>14.00</i>	<i>42.00</i>
CHLORIDE	<i>5 ul</i>	@	<i>38.00</i>	<i>190.00</i>
ASC		@		

**RECEIVED**  
AUG 05 2005  
KCC WICHITA

EQUIPMENT

PUMP TRUCK CEMENTER *Jack*

# *224* HELPER *Jim*

BULK TRUCK

# *260* DRIVER *Ricky*

BULK TRUCK

# DRIVER

HANDLING	<i>163 ul</i>	@	<i>1.60</i>	<i>260.80</i>
MILEAGE	<i>163.44</i>	@	<i>2.10</i>	<i>342.30</i>
TOTAL				<i>2183.60</i>

**REMARKS:**

*Run 5 jts of 8 5/8 csg - cement with 125 sy cement - Displace plug with 13 BBLS of fresh water. Cement did Cure.*

*Thanks*

CHARGE TO: *Mull Oalg co.*

STREET

CITY STATE ZIP

**SERVICE**

DEPTH OF JOB	<i>208'</i>			
PUMP TRUCK CHARGE				<i>670.00</i>
EXTRA FOOTAGE		@		
MILEAGE	<i>35</i>	@	<i>5.00</i>	<i>175.00</i>
TOTAL				<i>845.00</i>

**PLUG & FLOAT EQUIPMENT**

MANIFOLD/		@		
<i>1 - 8 5/8 wood</i>		@	<i>55.00</i>	<i>55.00</i>
TOTAL				<i>55.00</i>

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.


TAX

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS

SIGNATURE

PRINTED NAME



CHARGE TO *Mull Dots*  
 ADDRESS  
 CITY, STATE, ZIP CODE

TICKET No 8033

PAGE 1 OF 1

SERVICE LOCATIONS  
 1. *27451/13*  
 2. *NESSC174/13*  
 3.  
 4.

WELL/PROJECT NO. *1-28* LEASE *Koifschneider* COUNTY/PARISH *Lane* STATE *Ks* CITY DATE *06-23-05* OWNER  
 TICKET TYPE  SERVICE  SALES CONTRACTOR RIG NAME/NO *MullWellServ.* SHIPPED *VIA 6.7* DELIVERED TO *4211/14, Ninto Dighton Ks* ORDER NO.  
 WELL TYPE *Dil* WELL CATEGORY *Devlop* JOB PURPOSE *CMT. Port Coller* WELL PERMIT NO. WELL LOCATION  
 REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.	UM	QTY.	UM	UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE #105	10	mi			4.00	160.00
578		1			Pump Service	1	eq	2025	FT	1250.00	1250.00
330		2			SMD Contract	230	shs			10.50	2415.00
276		2			Fluocole	59	lbs			1.00	59.00
581		2			Service Chg CMT	235	shs			1.10	258.50
583		2			Drayage	469.3	Ton			1.00	469.30
104		2			Port Coller Tool Repair	1	eq	5 1/2	in	250.00	250.00

RECEIVED  
 AUG 05 2005  
 KCC WICHITA  
 KCC  
 AUG 03 2005  
 CONFIDENTIAL

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

*[Signature]*  
 DATE SIGNED *06-23-05* TIME SIGNED *1400*  A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	AMOUNT
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?					
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES	<input type="checkbox"/> NO			
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL	5006.17

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR *[Signature]* APPROVAL

Thank You!

CONFIDENTIAL

07/08/2005 07:19 FAX 1 719 767 8994 MDC-CHEM WELLS CO MDC-WICHITA-LOG 14001

CUSTOMER *Mud Dots* WELL NO. *1-28* LEASE *Reifschneider* JOB TYPE *CMT Port Coller* TICKET NO. *8033*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	INB	CASING	
	1400							<p><b>KCC</b> <b>AUG 03 2005</b> <b>CONFIDENTIAL</b></p> <p>Drivlocation, discuss Job, &amp; materials 5 1/2 15.5' /m 606 2 3/8" 8 7/8" 203 FT Port Coller @ 2075 Locate P.C.</p>
	1420			✓	✓	1000	1000	Pressure Test T <sub>hy</sub> -C.S.G.
	1422	3.0	3	✓		400		Open P.C.
	1425	3.0	0	✓		400		Start Mixing CMT @ 11.2 gal/sec 2045 hrs
		4.5	11	✓		500		Circ to pit Mud
		4.5	79	✓		500		
		4.5	143	✓	-	500		Circ CMT to pit - air 13.0 gal CMT
		4.0	121	✓		500		end CMT 265 hrs
		4.0	0	✓		500		Start Disp.
		4.0	7.0	✓		500		end Disp.
								Close P.C. Total CMT 230
	1500			✓	✓	1000	1000	Pressure up PC Closed
								Release PST
								Run 5 Joint
	1510	2.5	0	✓		400		Run out
			7.5	✓				1st CMT Flg
		2.5	90	✓		300		Clean
			110	✓				2nd CMT Flg
		2.5	130	✓		250		Clean
	1520	2.5	200	✓		250		All Clean
	1525							Wash up T <sub>hy</sub> P=11 P.C. T=1
	1540							Rock up
								Tick Mark
	1600							Job Complete

Thank You!  
Dave, Blaine, Brett

# ALLIED CEMENTING CO., INC

17196

**CONFIDENTIAL**

**KCC**

**ORIGINAL**

AUG 03 2005

SERVICE POINT:

*News City*

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

**CONFIDENTIAL**

DATE <u>6-19-05</u>	SEC. <u>28</u>	TWP. <u>17</u>	RANGE <u>28</u>	CALLED OUT <u>2:00 AM</u>	ON LOCATION <u>4:15 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>1:45 PM</u>
LEASE <u>Reifschneider</u>			WELL # <u>1-28</u>	LOCATION <u>Dighton golf course 1/4 E, 4 N, 2 W</u>		COUNTY <u>Lamar</u>	STATE <u>Ka</u>
OLD OR <u>(NEW)</u> (Circle one)		<u>1/4 N</u>					

CONTRACTOR Duke  
 TYPE OF JOB Longstring  
 HOLE SIZE 7 7/8 T.D. 4580'  
 CASING SIZE 5 1/2 DEPTH  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL Port collar 2130' DEPTH 2130'  
 PRES. MAX 1100\* MINIMUM  
 MEAS. LINE NO SHOE JOINT 35.5  
 CEMENT LEFT IN CSG.  
 PERFS.  
 DISPLACEMENT 10% 78LS

OWNER Mull Drilling Co, Inc.

CEMENT  
 AMOUNT ORDERED 130 AX ASC 2% GEL  
1/4# floccul per ax .005% FL 160

EQUIPMENT  
News  
 PUMP TRUCK CEMENTER Jim W  
 # 224 HELPER  
 BULK TRUCK DRIVER Steve T  
 # 341  
 BULK TRUCK DRIVER  
 #

COMMON	@		
POZMIX	@		
GEL <u>3.4%</u>	@	<u>14.00</u>	<u>42.00</u>
CHLORIDE	@		
ASC <u>130 Dalk</u>	@	<u>10.75</u>	<u>1397.50</u>
<u>Salt 703#</u>	@	<u>5.75</u>	<u>123.33</u>
<u>Fl-160 61#</u>	@	<u>8.70</u>	<u>530.70</u>
<u>Fl-SEAL 33#</u>	@	<u>1.70</u>	<u>56.10</u>
<b>RECEIVED</b>			
AUG 05 2005			
<b>KCC WICHITA</b>			
HANDLING <u>143.44</u>	@	<u>1.60</u>	<u>229.50</u>
MILEAGE <u>143.44 06</u>	@	<u>35</u>	<u>300.30</u>
		TOTAL	<u>2678.13</u>

**REMARKS:**

*From 1397 ft 5 1/2 casing, found split 5 1/2 pipe,  
 Came back out of hole & layed down casing,  
 Re-tallied casing. No back in hole, pipe on bottom.  
 Hook up + pump bell, Cmc wrap + then mud to spec.  
 Circ 45 min, pump 5 bbls b<sup>100</sup> ahead, pump 1000 gallons  
 flush, with 5 bbls behind, change valves over + release  
 bottom plug, close in + plug girth hole, wash lines + pump out  
 lead top plug. Mixed BSC, shot down, change valves over +  
 release, 5 1/2 Rubber plug, Wash out pump + lines, displace 95  
 barrels + stop rotating head. Sand plug with 1 1/2 b<sup>100</sup>  
 do not hold. Shift in at ment told to have head on.*

CHARGE TO: Mull Drilling Co, Inc.  
 STREET P.O. Box 2758  
 CITY Wichita STATE Ka ZIP 67201-2758

**SERVICE**

DEPTH OF JOB <u>4575.5'</u>		
PUMP TRUCK CHARGE		<u>1435.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>33</u>	@	<u>5.00 175.00</u>
Rubber Bottom plug	@	<u>59.00 59.00</u>
Rubber Top plug	@	<u>60.00 60.00</u>
Rotating head	@	<u>75.00 75.00</u>
		TOTAL <u>1804.00</u>

**PLUG & FLOAT EQUIPMENT**

1-5 1/2 thide, plug		<u>160.00 160.00</u>
MANIFOLD 1-Float collar	@	<u>265.00 265.00</u>
15-Centralliners	@	<u>50.00 750.00</u>
1-Basket	@	<u>140.00 140.00</u>
1-Port Collar	@	<u>175.00 175.00</u>
12-Rotating scratcher	@	<u>45.00 540.00</u>
		TOTAL <u>3605.00</u>

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment  
 and furnish cementer and helper to assist owner or  
 contractor to do work as is listed. The above work was  
 done to satisfaction and supervision of owner agent or  
 contractor. I have read & understand the "TERMS AND  
 CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

X Jim Crombie  
 PRINTED NAME



CHARGE TO: MULL DRUG Co.  
 ADDRESS: \_\_\_\_\_  
 CITY, STATE, ZIP CODE: \_\_\_\_\_

TICKET No 8536

PAGE 1 OF 1

SERVICE LOCATIONS: Ness City, KS  
 WELL/PROJECT NO.: 1-28 LEASE: Heifschneider COUNTY/PARISH: WJE STATE: Ks CITY: \_\_\_\_\_ DATE: 6-18-05 OWNER: same  
 TICKET TYPE:  SERVICE SALES CONTRACTOR: DURE DRUG RIG NAME/NO.: \_\_\_\_\_ SHIPPED VIA: \_\_\_\_\_ DELIVERED TO: PICKED UP - GABLES ORDER NO.: \_\_\_\_\_  
 WELL TYPE: OIL WELL CATEGORY: DEVELOPMENT JOB PURPOSE: 5/2" LONGSTRONG WELL PERMIT NO.: \_\_\_\_\_ WELL LOCATION: NE / NESS CITY, KS  
 REFERRAL LOCATION: \_\_\_\_\_ INVOICE INSTRUCTIONS: \_\_\_\_\_

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF			UM		UM	
502					MILEAGE LOAD CHARGE	1		60.00		60.00
280					FLOCHECK-21	1000	64	2.00		2000.00

RECEIVED  
 AUG 05 2005  
 KCC WICHITA

KCC  
 AUG 03 2005  
 CONFIDENTIAL

TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

DATE SIGNED: 6-18-05 TIME SIGNED: 1900  
 A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	AMOUNT
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?					
ARE YOU SATISFIED WITH OUR SERVICE?	<input checked="" type="checkbox"/> YES		<input type="checkbox"/> NO		
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL	2166.00

Lane TAX 5.3% 106.00

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES  
 SWIFT OPERATOR: WANE WISOR APPROVAL: \_\_\_\_\_

Thank You!