

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01341-00-00
Spot: SENENW Sec/Twnshp/Rge: 6-24S-5E
4198 feet from S Section Line, 3013 feet from E Section Line
Lease Name: CLAASSEN Well #: 5
County: BUTLER Total Vertical Depth: 2471 feet

Operator License No.: 5387

Op Name: THE BUCKEYE CORPORATION DBA AZTEC OIL CO. DIVISION

Address: PO BOX 1020
EL DORADO, KS 67042

\$ 80.31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/06/2007 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-5-2007 RIH W/TBG @ 2435', ESTABLISHED CIRCULATION, AND HURRICANE WELL SERVICE MIXED & PUMPED 40 SKS CLASS A 2% CC, WAITED 2 HRS, RIH W/TBG @ 2249', CIRCULATED HOLE CLEAN WITH CEMENT RETURNS, 4-6-2007, SHOT 7" CASING @ 780' & 302', LAYED DOWN 10 JTS (302') 7" CASING, RIH W/TBG @ 275', HURRICANE WELL SERVICE MIXED & PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED, P.A. COMPLETE 1400 04-06-2007. HURRICANE WELL SERVICE CEMENT TICKET #1816.

Perfs:

INVOICED
DATE 6-28-07
INV. NO. 2007061945

Remarks: -096.92438..37.99595, OPEN HOLE 2460'-2471'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 28 2007

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

CONSERVATION DIVISION
WICHITA, KS

PKT