

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01342-00-00
Spot: SESENW Sec/Twnshp/Rge: 6-24S-5E
2891 feet from S Section Line, 3019 feet from E Section Line
Lease Name: CLAASSEN Well #: 6
County: BUTLER Total Vertical Depth: 2489 feet

Operator License No.: 5387

Op Name: THE BUCKEYE CORPORATION DBA AZTEC OIL CO. DIVISION

\$ 80.89

Address: PO BOX 1020
EL DORADO, KS 67042

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/10/2007 8:00 AM

Plug Co. License No.: 32006

Plug Co. Name: HURRICANE WELL SERVICE, INC.

Proposal Rcvd. from: STEVE KILE

Company: AZTEC OIL CO.

Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RELES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/11/2007 2:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

4-10-27, RIH W/TBG @2358', HURRICANE WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A 2% CC, WAITED 2 HRS, RIH W/TBG @ 2203', CIRCULATED HOLE CLEAN, WITH CEMENT RETURNS, 4-11-2007, SHOT 7" CSG @ 308', LAYED DOWN 9 JTS, (308') 7" CSG. RIH W/TBG @ 275', HURRICANE WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED TO SURFACE P.A. COMPLETE 1400 04-11-2007. HURRICANE WELL SERVICE CEMENT TICKET #1826.

INVOICED
DATE 6-28-07
INV. NO. 2007061945

Remarks: -096.92440,37.99236 OPEN HOLE 2479'-2489'

Plugged through: TBG

District: 02

Signed

Duane Krueger

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

PKT