

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01344-00-00
Spot: SWSENW Sec/Twnshp/Rge: 6-24S-5E
2906 feet from S Section Line, 3685 feet from E Section Line
Lease Name: CLAASSEN Well #: 8
County: BUTLER Total Vertical Depth: 2467 feet

Operator License No.: 5387

Op Name: THE BUCKEYE CORPORATION DBA AZTEC OIL CO. Division

Address: PO BOX 1020
EL DORADO, KS 67042

\$ 80.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/16/2007 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

4-12-2007, RIH W/TBG @ 2426' ESTABLISHED CIRCULATION, HURRICANE WELL SERVICE MIXED & PUMPED 40 SXS CLASS A 2% CC, WAITED 2 HOURS, RIH W/TBG @ 2240', CIRCULATED HOLE CLEAN, WITH CEMENT RETURNS, 4-16-2007, SHOT 7" CASING @ 310', LAYED DOWN 9 JTS, (310') 7" CASING, RIH W/TBG @ 275' ESTABLISHED CIRCULATION, HURRICANE WELL SERVICE MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED TO SURFACE. P.A. COMPLETE 1500 4-16-2007. HURRICANE WELL SERVICE CEMENT TICKET #1827.

INVOICED
DATE 6-28-07
INV. NO. 2007061945

Remarks: -096.92671,37.99240 OPEN HOLE 2454'-2467'

Plugged through: TBG

District: 02

Signed *Duane Krueger*
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]