

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01346-00-00
Spot: SESWNW Sec/Twnshp/Rge: 6-24S-5E
2898 feet from S Section Line, 4334 feet from E Section Line
Lease Name: CLAASSEN Well #: 10
County: BUTLER Total Vertical Depth: 2463 feet

Operator License No.: 5387

Op Name: THE BUCKEYE CORPORATION DBA Aztec oil co. Division.

\$ 80.05

Address: PO BOX 1020
EL DORADO, KS 67042

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/18/2007 7:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

4-17-2007, RIH W/TBG @ 2328', ESTABLISHED CIRCULATION, HURRICANE WELL SERVICE MIXED & PUMPED 40 SXS CLASS A 2%CC, WAITED 2 HOURS. RIH W/TBG @ 2142', CIRCULATED HOLE CLEAN, WITH CEMENT RETURNS, 4-18-2007, SHOT 7" CASING @ 307', LAYED 10 JTS (307') 7" CASING, RIH W/TBG @ 275', ESTABLISHED CIRCULATION, HURRICANE MIXED & PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT DID CIRCULATE, P.A. COMPLETE 1900 04-18-2007, HURRICANE WELL SERVICE CEMENT TICKET #1828.

INVOICED
DATE 6-28-07
INV. NO. 2007061945

Remarks: -096.92896,37.99238 OPEN HOLE 2452'-2463'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED KANSAS CORPORATION COMMISSION JUN 28 2007 CONSERVATION DIVISION WICHITA, KS
RECEIVED KANSAS CORPORATION COMMISSION JUN 19 2007 CONSERVATION DIVISION WICHITA, KS
Form CP-2/3

PKS