

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20568-00-01  
Spot: SESENW Sec/Twnshp/Rge: 7-1S-34W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SRAMEK A Well #: 1  
County: RAWLINS Total Vertical Depth: 4318 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4317	0	w/150 sxs cmt
SURF	8.625	259	0	w/185 sxs cmt
T1	2.875	4272		Lost circ during cementing of tbg. Sqz leak at 3870' w/100 sx. Backside sqz from 2570' to 600' w/75 sx & at 600' w/25 sx not to surface.5/26/05.OR.

*\$ 140.34*

Well Type: EOR UIC Docket No: E25175.1 Date/Time to Plug: 06/06/2007 9:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: ED HAYNES Company: BEREXCO, INC. Phone: (308) 340-6288

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel and 150# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2007 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 259' w/185 sxs cement.  
4 1/2" production casing set at 4317' w/150 sxs cement.  
2 7/8" tubing cemented in production casing and set at 4272'.  
2 7/8" tubing perforated from 4125' - 4131'.  
Connected to 2 7/8" tubing and pumped 160 sxs cement with 150# hulls.  
Max. P.S.I. 600#. S.I.P. 0#.  
Connected to 8 5/8" surface pipe and pumped 40 sxs cement.  
Max. P.S.I. 100#. S.I.P. 0#.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 28 2007  
CONSERVATION DIVISION  
WICHITA, KS  
**INVOICED**  
DATE 6-28-07  
INV. NO. 2007061946

Remarks: ALLILED CEMENTING COMPANY-TICKET #28,565.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

JUN 13 2007

PPT

ABRAXAS PETROLEUM CORPORATION

7-1-34W

P. O. BOX 17485

#1 "A" SRAMEK

SE SE NW


SAN ANTONIO, TX 78217

CONTR MURFIN DRILLING CO.

CTY RAWLINS

GEOLOGIST BOB DILTS

FIELD CAHOJ NW



ELV 3127 KB SPD 10/4/84 CARD ISSUED 3/7/85 IP P 3.48 BO & 3.48

3122 GL  
API 15-153-20,568

BWPD  
LKC "C" 4126-4131

SMP	Tops	Depth/Datum	
ANH		2977+ 150	8 5/8 " 259 / 185SX, 4 1/2 " 4317 / 150SX
B/ANH		3014+ 113	DST (1) 3875-3930 (SHAW) / 30-60-60-90, REC 164' OCWM (10% OIL, 30% W, 60% M), 62' OCWM (20% OIL, 20% W, 60% M), 186' OCMW (10% OIL, 60% W, 30% M), 248' SOCMW (5% OIL, 80% W, 15% M), SIP 1175-1165#, FP 84-222 / 130-317#, HP 1991-1990#
CHASE		3207- 80	
NEVA		3487- 360	
RED E		3551- 424	
FOR		3605- 478	DST (2) 4082-4145 (LKC C) / 30-45-30-45, REC 60' OIL SPK MW (60% W, 40% M), 70' MW (75% W, 25% M), 6 INCHES FREE OIL ON TOOL, SIP 773-667#, FP 74-74 / 105-105#, HP 2097-2076#
TOP		3815- 688	
DR CR		3852- 725	
OREAD		3907- 780	DST (3) 4143-4243 (LKC D&E) / 30-45-45-45, REC 120' M, W / FEW OIL SPKS, SIP 614-614#, FP 84-84 / 105-105#, HP 2118-2086#
HEEB		3965- 838	
B/OREAD		3978- 851	
LANS		4024- 897	MITC - CO, PF (LKC) 4260-64, W / 4 SPF, AC 500G, SWB DWN, PF (LKC) 4216-23, W / 4 SPF, AC 500G, SWB DWN, PF (LKC) 4178-82, W / 4 SPF, AC 500G, SWB DWN, PLUGGED OFF ABOVE PFS, PF (LKC) 4126-31, W / 4 SPF, AC 500G, SWB DWN, GSO, T&R, POP, P 3.48 BO & 3.48 BWPD, 1/17/85
LKC B		4077- 950	
LKC C		4126- 999	
LKC D		4178-1051	
BKC		4294-1167	LTD ..... 4318-1191 RTD ..... 4320-1193

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS