

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23616-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 2-14S-17W
3480 feet from S Section Line, 628 feet from E Section Line
Lease Name: OLIVER KUHN Well #: 1
County: ELLIS Total Vertical Depth: 3496 feet

Operator License No.: 32504
Op Name: WERTH, AARON J. DBA BLACKHAWK
Address: 1607 OAKMONT
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3483	0	w/125 sxs cmt
SURF	8.625	207	0	w/150 sxs cmt

\$ 113.62

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2007 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: AARON J. WERTH Company: BLACKHAWK PRODUCTION COM Phone: (785) 650-1782

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug down casing. Backside full.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2007 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Dug out well head - found backside full of cement.
Tied onto the casing and pumped 225 sxs cement with 500# hulls.
Max. P.S.I. 700#. S.I.P. 400#.

Perfs:

INVOICED
DATE 6-28-07
INV. NO. 2007061949

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1535.

Plugged through: CSG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUN 18 2007

PT

EDWARD P. LEIKER
 MUNJOR RT., BOX 17 #1 KUHN 2-14-17W
 HAYS, KS 67601 1800' FNL &
 CONTR RED TIGER DRILLING CO. CTY ELLIS 628' FEL, NE/4
 GEOL _____ FIELD TOULON
 ELV NA SPD ^E 9/25/83 CARD ISSUED 9/6/84 IP OIL WELL
 LKC - INTV NA
 API 15-051-23,616

	+	+	+
+	+	+	+
+	+	+	+

Tops	Depth/Datum
NO TOPS AVAILABLE	
E RTD	3540

E 8 5/8 " 200, PROD CSG NA
 MICT - CO, PF (LKC) INTV NA. SWB DWN, SO, POP - TIGHT
 HOLE - NO OTHER INFO TO BE RELEASED AT PRESENT - WILL
 RELEASE INFO WHEN AVAILABLE - TEMP COMP - 9/6/84

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

replacement card

EDWARD PLEIKER 2-14S-17W
 HAYS KS 1800' FNL & 628' FEL, SEC
 #1 KUHN, OLIVER
 site: 1/2 N & 1 W OF VICTORIA KS CTY: ELLIS API 15-051-23616
 contr: RED TIGER DRLG field: TOULON
 geol: _____
 date 09/19/83 spd date 09/28/83 dirg comp 10/04/83 card issued 09/06/84 last revised 10/12/98

ELV: 1931 KB, 1926 GL DRLRS	IP status:
tops.....depth/datum	OIL, P 30 BO & 30 BWPD, LKC 3221-3268 OA, 11/03/83
ANH.....1098 + 833	INFO RELEASED: 10/12/98 - WAS OIL WELL - TEMP
B/ANH.....1141 + 790	COMP
ARB.....3480 -1549	CSG: 8-5/8" 207 / 150 SX, 4-1/2" 3483 / 125 SX
RTD.....3496 -1565	NO CORES
	DST (1) 3470-3495 (ARB), / 30-30-30-30, (1ST OP) WB,
	(2ND OP) NB, REC 5' OCM, FP NA ISIF 1125# FSIP
	1110#
	MICT - CO, (ARB OH), AC 1000 GAL (15% MA), NON-
	COMMERCIAL, PF (LKC) 3264-3268, W / 2 SPF, AC 1000
	GAL (15% REG), SO, PF (LKC) 3221-3225, W / 2 SPF, AC
	1000 GAL (15% REG), SO, SET 2-3/8" TBG AT 3485, NO
	PKR, POP, IPP 30 BO & 30 BWPD (GR 33), DOFP 11/3/83
	- NO OTHER INFO AVAILABLE

COPYRIGHT 1988
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS