

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23811-00-00
Spot: SWSESENE Sec/Twnshp/Rge: 2-14S-17W
2740 feet from S Section Line, 410 feet from E Section Line
Lease Name: OLIVER KUHN Well #: 2
County: ELLIS Total Vertical Depth: 3525 feet

Operator License No.: 32504
Op Name: WERTH, AARON J. DBA BLACKHAWK
Address: 1607 OAKMONT
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3503	0	w/125 sxs cmt
SURF	8.625	217	0	w/150 sxs cmt

\$114.50

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2007 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: AARON Company: BLACKHAWK PRODUCTION COM Phone: (785) 650-1782

Proposed Plugging Method: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug down the top.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2007 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Dug out well head - found cement on backside.
Pumped 240 sxs cement with 500# hulls down the casing.
Squeezed Max. P.S.I. 1200#. S.I.P. 800#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 18 2007

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 20 2007

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 6-28-07

INV. NO. 2007061949



EDWARD P. LEIKER
MUNJOR RT., BOX 17
HAYS, KS 67601


#2 OLIVER KUHN

2-14-17W
2540' FNL &
410' FEL, NE/4

CONTR RED TIGER DRLG. CO. CTY ELLIS

GEOL _____ FIELD TOULON

ELV 1930 KB SPD 2/29/84 CARD ISSUED 8/2/84 IP P 14 BO & 42 BWPD
LKC 3217-3266 OA



SMP	Tops	Depth/Datum
*ANH	1097 + 833
*B/ ANH	1139 + 791
HEEB	3147-1217
LANS	3192-1262
BKC	3426-1496
CONG	3440-1510
ARB	ABSENT
RTD	3525-1595
* DRILLERS TOPS		
NO LOG		

API 15-051-23,811
8 5/8 " 217/150SX, 4 1/2 " 3503/125SX
NO DST'S
NS IN SD FROM 561-738
MIGT - CO, PF (PENN) 3433-35 W/2 SPF, AC 250G (INS), SWB LD, NS, PF (LKC) 3261-66 W/2 SPF, AC 1000G (INS), SWB LD, SO, PF (LKC) 3217-22 W/2 SPF, AC 1000G (INS), SWB LD, SO, SET 2 3/8 " TBG AT 3442', POP, P 14 BO & 42 BWPD (GR 34°), 5/31/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS