

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21390-00-00  
Spot: SWSW Sec/Twnshp/Rge: 25-32S-9W  
572 feet from S Section Line, 4747 feet from E Section Line  
Lease Name: KNOX A Well #: 1  
County: HARPER Total Vertical Depth: 3705 feet

Operator License No.: 8740  
Op Name: BRAMWELL PETROLEUM, INC.  
Address: 15183 SW 25TH AVE.  
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3703		150 SX CMT
SURF	8.625	261		175 SX CMT

\$120.41

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2007 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PERFS 3694-97' PBTD, 3702' SAND BACK 50' ABOVE PERFS, CAP WITH 4 SKS OF CMT, 35 SKS 1400', 35 SKS 800', CIRC 320'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/01/2007 12:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM 3702' TO 3640', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2480', AND PULLED TO 1400', WHERE 1 SK OF HULLS AND 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 800', WHERE 2 SKS OF HULLS WERE AND 35 SKS OF CMT WERE SPOTTED. THE CASING WAS PULLED TO 320', WHERE 2 SKS OF HULLS WERE SPOTTED AND CMT WAS CIRC. TO SURFACE. -98.25500,37.22632.

Perfs:

**INVOICED**  
DATE 6-28-07  
INV. NO. 2007061950

Remarks: UNITED CMTG 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED KANSAS CORPORATION COMMISSION  
RECEIVED KANSAS CORPORATION COMMISSION  
FORM CP-2/3

JUN 28 2007

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

CONSERVATION DIVISION  
WICHITA, KS