

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20513-00-01  
Spot: SE Sec/Twnshp/Rge: 34-28S-8W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: ROHLMAN Well #: 1  
County: KINGMAN Total Vertical Depth: 4140 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT STREET, SUITE 1500  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4137	<u>2124</u>	150 SX CMT ASC GS CL 7%.
SURF	8.625	208		

*per operator  
KCC PKT 6/27/07 \$134.55*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2007 10:00 AM  
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC  
Proposal Rcvd. from: JOE BORLA Company: CORAL PRODUCTION CORPORATI Phone: (303) 601-5823

Proposed Plugging Method: 50' SAND PLUG OVER PERFS @ 4118'-22'; 10 SKS ON TOP OF SAND; STRETCH CSG & SHOOT OFF; 30 SKS AT BASE OF SURFACE CSG, 1/2 IN, 1/2 OUT; 10SKS@ SURFACE; CUT CSG 4' BELOW GRADE 7 WELD CAP.

Plugging Proposal Received By: BILLIE J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/26/2007 10:00 AM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

Sanded back to 4075 - topped with 6 sks of cement. Shot off casing @2124' with wireline Co. from Hays KS (Pert-Tech) - pulled casing to 1175' spotted 35 sks of cement- pulled casing to 750' spotted 35 sks of cement, pulled casing to 325' circ. Cement to surface with 130 sks of cement- Fell back to 50' no fluid, added 15 sks cement to of surface. finished AM of the 27th

Perfs:

Top	Bot	Thru	Comments
4118	4122		

**INVOICED**  
DATE 6-28-07  
INV. NO. 2007061952

Remarks: ALLIED CEMENT- MEDICINE LODGE, KS TICKET 32411 60/40 POZMIX 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]

(TECHNICIAN)  
RECEIVED KANSAS CORPORATION COMMISSION RECEIVED KANSAS CORPORATION COMMISSION

JUN 28 2007

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten mark]*