

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07837-00-00
Spot: NENW Sec/Twnshp/Rge: 23-15S-14W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: RESNER Well #: 5
County: RUSSELL Total Vertical Depth: 3367 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S. MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3358	0	w/unknown sxs cmt
SURF	8.625	369	0	w/unknown sxs cmt

\$ 109.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2007 3:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2007 4:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Well had drill collar and bit stuck in the hole at approximately 776'.
Ran tubing to 750' - circulated with 80 sxs 60/40 pozmix - 10% gel cement.
POOH. Tied onto 5 1/2" - pumped 120 sxs cement.
Max. P.S.I. 600#. S.I.P. 400#.
Well has been squeezed.

Perfs:

INVOICED
DATE 6-28-07
INV. NO. 2007061953

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: TBG

District: 04

W.

Signed

Case Morris

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

JUN 19 2007 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

CONSERVATION DIVISION
WICHITA, KS

JUN 13 2007

W.

REPUBLIC NAT'L GAS CO #5 RESNER 23-15-14W
 G. NE NW


Contr. _____ RUSSELL County

E 1909 Comm. 6-29-42 Comp. 7-29-42 IP 121.09 BOPD

Tops	Depth	Datum
ANHY	919	
LANS	3111	-1702
ARB	3358	-1449
TD	3367	-1458

Casing
 8" 369
 5" 3358

A/2000 & 500
 Butane 750
 PAY 3358-67



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS