

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23309-00-00
Spot: NENWSES Sec/Twnshp/Rge: 11-9S-22W
1090 feet from S Section Line, 1890 feet from W Section Line
Lease Name: VAN LOENEN Well #: 1
County: GRAHAM Total Vertical Depth: 3916 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220	0	

\$ 127.27

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/13/2007 5:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 06/13/2007 7:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3842' w/25 sxs.
2nd. Plug at 1800' w/25 sxs.
3rd. Plug at 1025' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 6-28-07
INV. NO. 2007061957

Form CP-2/3

JUN 19 2007

[Handwritten signature]