

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21317-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 16-31S-8W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HOSTETLER Well #: 3-16  
County: HARPER Total Vertical Depth: 4475 feet

Operator License No.: 33513  
Op Name: FIVE STAR ENERGY, INC.  
Address: 215 E. 14TH ST.  
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4474		125 SX
SURF	8.625	200		170 SX

\$ 145.44

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: HOWARD SHORT Company: QUALITY WELL SERVICE, INC. Phone: (620) 896-2710

Proposed Plugging Method: PER KCC REGULATIONS.

Plugging Proposal Received By: BILLIE J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/26/2007 4:00 PM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

SHOT AND PULLED CASING FROM 2880'-USED CASING TO SPOT CEMENT FOR PLUGGING. SAND TO 4025' 4 SKS CEMENT SPOTTED. SPOTTED 35 SKS AND 150 LBS OF HULLS @ 1350', AT 850' SPOTTED 35 SKS OF CEMENT AND 150 LBS OF HULLS, AT 250' CIR. 125 SKS OF CEMENT AND 50 LB OF HULLS -

Perfs:

Top	Bot	Thru	Comments
4423	4424		
4363	4378		
4076	4084		

**INVOICED**  
DATE 6-28-07  
INV. NO. 2007061957

Remarks: FELL BACK 150' ON 03-27-07 CIR TO CEMENT TO SURFACE. SURFACE 04/06/07 -UNTIED CEMENTING TICKET #7682 60/40 POZMIX 4% GEL

Plugged through: CSG

District: 02

Signed

B. J. Hope

RECEIVED (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

RECEIVED

KANSAS CORPORATION COMMISSION

JUN 19 2007

JUN 28 2007

CONSERVATION DIVISION  
WICHITA, KS

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3