

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21503-00-00
Spot: E2SENE Sec/Twnshp/Rge: 10-31S-7W
1980 feet from N Section Line, 330 feet from E Section Line
Lease Name: MATHES Well #: 1-10
County: HARPER Total Vertical Depth: 4448 feet

Operator License No.: 33513
Op Name: FIVE STAR ENERGY, INC.
Address: 215 E. 14TH ST.
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4447		175 SX CMT
SURF	8.625	254		225 SX CMT

\$ 144.50

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/10/2007 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD. Company: QUALITY WELL SERVICE, INC. Phone: (620) 896-2710

Proposed Plugging Method: PER KCC REGULATIONS.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 04/10/2007 1:00 PM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

4-6-07 SANDED BACK TO 4280' TOPPED W/5 SKS OF CEMENT. RIPPED OFF PIPE @ 3080. 4-10-07 PULLED CASING TO 1250' SPOTTED 35 SKS CEMENT & 150 LBS. HULLS. PULLED CASING TO 800' SPOTTED 35 SKS CEMENT 100 LB HULLS. PULLED CASING TO 300' CIRC. CEMENT TO SURFACE USED 85 SKS CEMENT AND 50 LBS OF HULLS.

Perfs:

Top	Bot	Thru	Comments
4337	4341		

INVOICED

DATE 6-28-07
INV. NO. 2007061959

Remarks: UNTED CEMENT COMPANY TICKET # 7687 CEMENT 60/40 POZMIX W/4% GEL

Plugged through: CSG

District: 02

Signed _____

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

pet