

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01909-00-01
Spot: SENENW Sec/Twnshp/Rge: 7-10S-19W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: OUDEKIRK Well #: 4
County: ROOKS Total Vertical Depth: 3364 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: 130 E. ROSS, SUITE 103
CLEARWATER, KS 67026

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3768	0	w/unknown sxs cmt
SURF	8.625	187	0	w/unknown sxs cmt

\$ 109.33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2007 1:30 PM
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.
Proposal Rcvd. from: AL HAMMERSMITH Company: H&B PETROLEUM CORPORATION Phone: (620) 584-6380

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Washed down ran out of casing at 3364'.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/18/2007 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3200'. Rigged to tubing and pumped 50 sxs 60/40 pozmix with 100# hulls.
Pulled tubing to 1750' - pumped 130 sxs cement with 300# hulls mixed in - cement circulated to surface.
Hole standing full.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #22079.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 6-28-07
INV. NO. 2007061962

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 19 2007

NADEL & GUSSMAN

#4

22
OUDERKIRK

7-10-19W
SE NE NW

Contr. RESERVE DRILLING CO.

ROOKS

County

E 2228

Comm.

Comp.

7-29-49

IP

3000 BOPD

Tops	Depth	Datum
HEEB	3435	- 1207
LANS	3473	- 1245
CONG	3709	- 1481
SIMP DOL	3754	- 1526
ARB	3766	- 1538
T.D.	3773	- 1545

Casing
8" 187
5" 3766

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS