

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23415-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 28-15S-14W  
550 feet from N Section Line, 2170 feet from E Section Line  
Lease Name: RADKE Well #: 1  
County: RUSSELL Total Vertical Depth: 3370 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718-183RD ST. PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	461	0	

# 109.53

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2007 3:45 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 145 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 06/01/2007 6:45 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3250' w/25 sxs.  
2nd. Plug at 875' w/25 sxs.  
3rd. Plug at 515' w/60 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 6-28-07  
INV. NO. 2007061963

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 20 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 28 2007

CONSERVATION DIVISION  
WICHITA, KS

JUN 19 2007

PAF