

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-02771-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 15-20S-10W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: LINKE Well #: 5  
County: RICE Total Vertical Depth: 3370 feet

Operator License No.: 9971  
Op Name: KODIAK PETROLEUM, INC.  
Address: PO BOX 4677  
ENGLEWOOD, CO 80155

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3370		125 SX
SURF	8.625	184		150 SX

*\$109.53*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2007 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/25/2007 12:30 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

CIBP @ 2510', MIRU, 2.5" TUBING IN CASING STUCK. FREED UP AND PULLED OUT. RUN 2" TUBING BACK IN AND ENCOUNTERED OBSTRUCTION AT 900', RUN TUBING ON DOWN TO 1271' WHERE TUBING STACKED OUT HARD WHERE CASING WAS LIKELY PARTED. PERFORATED AT 1280' AND PUMP 100 SX'S CEMENT. PULL TUBING TO 900' AND PERFORATE, THEN PUMP 85 SX'S CEMENT. PULL TUBING TO 250' AND PERFORATE, THEN CIRCULATE CEMENT TO SURFACE. CONNECTED ON TO SURFACE CASING AND PUMPED 75 SX'S AT 300#S-HELD 300#S. TOPPED OFF 5.5"-10 SX'S.

**Perfs:**

Top	Bot	Thru	Comments
3367	3370		ARBUCKLE
2353	2354		
2340	2347		

**INVOICED**  
DATE 6-28-07  
INV. NO. 200 7061965

Remarks: 60-40 POZ, 4% GEL. COPELAND #C031808. LOG TECH 4948.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
RECEIVED (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

**JUN 28 2007**  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3  
**JUN 19 2007**  
CONSERVATION DIVISION  
WICHITA, KS

*PRG*