

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02775-00-00
Spot: NESESE Sec/Twnshp/Rge: 15-20S-10W
952 feet from S Section Line, 550 feet from E Section Line
Lease Name: LINKE Well #: 9
County: RICE Total Vertical Depth: 3379 feet

Operator License No.: 9971
Op Name: KODIAK PETROLEUM, INC.
Address: PO BOX 4677
ENGLEWOOD, CO 80155

\$ 109.82

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2007 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/23/2007 10:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2300' AND CAP WITH 5 SX'S CEMENT. CUT CASING @1400' AND PULL TO 1250' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 900' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

INVOICED
DATE 6-28-07
INV. NO. 200 7061965

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C031802.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION 2/3

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

Handwritten signature/initials