

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: KNIGHTON OIL COMPANY, INC.
 Address: 221 S. Broadway, Suite 710 Wichita, Kansas 67202
 Phone: (316) 264-7918 Operator License #: 5010
 Type of Well: ENHR Docket #: E-13935
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 7/6/07 (Date)
 by: Marvin Mills (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Conglomerate Depth to Top: 3783 Bottom: 3809 T.D. 3850'
Marmaton Depth to Top: 3726 Bottom: 3746 T.D. 3850'
Lansing Depth to Top: 3466 Bottom: 3476 T.D. 3850'

195-00940-00-01

API Number: 15 - drilled in 1954
 Lease Name: Holtzinger
 Well Number: 2
 Spot Location (QQQQ): C - SW - NW - SW
1650 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 35 Twp. 14 S. R. 21 East West
 County: Trego
 Date Well Completed: 10/27/54
 Plugging Commenced: 7/6/07
 Plugging Completed: 7/6/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	221'	10 3/4"	221'	None
		surface	3840'	7 "	3840'	None

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 13 2007
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing at 3573' spot 40 sacks with 350# hulls, pull up to 3223 pump 80bbbls of mud, pull up to 1925 mix 185 sacks with 250# hulls, circulate to surface, pull tubing to top, add 20sacks. Total of 245 sacks of 60/40 and 600# hulls.

Name of Plugging Contractor: Express Well Service License #: 6426
 Address: P.O. Box 19 Victoria, KS 67671
 Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc.
 State of Kansas County, Sedgwick, ss.

Earl M. Knighton, Jr (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

DAVID D. MONTAGUE
Notary Public - State of Kansas
My Appt. Expires 10-4-07

(Signature) *Earl M. Knighton, Jr.*
 (Address) 221 S. Broadway, Suite 710 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 13th day of July, 20 07
David D. Montague My Commission Expires: 10-4-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AK



INVOICE

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Invoice Number: 109105
Invoice Date: Jul 10, 2007
Page: 1

Voice: (785) 483-3887
Fax: (785) 483-5566

Bill To:
Knighton Oil Co., Inc.
710 Petroleum Bldg.
221 S. Broadway
Wichita, KS 67202

Federal Tax I.D.#: 20-5975804

Customer ID	Well Name# or Customer P.O.	Payment Terms	
Knig	Hozinger #2	Net 30 Days	
Sales Rep ID	Camp Location	Service Date	Due Date
	Russell	Jul 10, 2007	8/9/07

Quantity	Item	Description	Unit Price	Amount
147.00	MAT	Common	11.10	1,631.70
98.00	MAT	Pozmix	6.20	607.60
17.00	MAT	Gel	16.65	283.05
6.00	MAT	Hulls	25.50	153.00
268.00	SER	Handling	1.90	509.20
55.00	SER	Mileage 268 sx @.09 per sk per mi	24.12	1,326.60
1.00	SER	Plug	720.00	720.00
55.00	SER	Mileage Pump Truck	6.00	330.00

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 13 2007
CONSERVATION DIVISION
WICHITA, KS

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 556.11

ONLY IF PAID ON OR BEFORE

Aug 9, 2007

Subtotal	5,561.15
Sales Tax	322.55
Total Invoice Amount	5,883.70
Payment/Credit Applied	
TOTAL	5,883.70

ALLIED CEMENTING CO., INC. 21194

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>7-6-07</u>	SEC. <u>35</u>	TWP. <u>14</u>	RANGE <u>21W</u>	CALLED OUT	ON LOCATION <u>9:00 Am</u>	JOB START	JOB FINISH <u>12:30 Pm</u>
LEASE <u>Hoizingen</u> WELL # <u>2</u>			LOCATION <u>Ellis 9 1/2 S 4 W 1/2 S</u>			COUNTY <u>rego</u>	STATE <u>Ks</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Express Plug

TYPE OF JOB _____

HOLE SIZE _____ T.D. _____

CASING SIZE 7" DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 13 2007
CONSERVATION DIVISION
WICHITA, KS

CEMENT AMOUNT ORDERED	<u>245 #H 6940 10</u>		
	<u>600 # Hubs</u>		
COMMON	<u>147</u>	@	<u>11.45</u>
POZMIX	<u>98</u>	@	<u>6.20</u>
GEL	<u>17</u>	@	<u>16.65</u>
CHLORIDE		@	
ASC		@	
<u>Hulls</u>	<u>6</u>	@	<u>25.50</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>268</u>	@	<u>1.90</u>
MILEAGE	<u>9 1/2 / SK / MILE</u>		<u>1326.40</u>
TOTAL			<u>4511.45</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

398 HELPER Gregory

BULK TRUCK DRIVER Chris B.

362 DRIVER _____

BULK TRUCK DRIVER _____

REMARKS:

Tub. c 3573 spot 40.0k
w/ 350 # Hubs
pull to 3223 pump 80 bbls
of mud, pull to 1425 mix 185.0k
w/ 250 # Hubs, Circ. TO SURFACE
(pull tubing) top of w/ 20.0k

SERVICE

DEPTH OF JOB	_____		
PUMP TRUCK CHARGE	<u>720.00</u>		
EXTRA FOOTAGE		@	
MILEAGE	<u>55</u>	@	<u>6.00</u>
MANIFOLD		@	
		@	
		@	
TOTAL			<u>1050.00</u>

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL		_____

CHARGE TO: Knights Oil

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

CASING RECORD

Size	Weight	No. Joints	Kind LW or SS New or SH	Casing Spot	Total Feet Run In	Total Feet Pulled	Total Feet Left In	No. Sacks Cement	Size Hole Casing Set In
0-3/4"	32.85	7	New SS	229	229	8	221	150	13-3/4"
"OD.	25 20	23 101	SH. SS NEW SS	3840	3850	15	3835	175	9"

Was temperature survey made? No Was pipe tallied over all or less threads Less threads

GUN PERFORATIONS

Date	Depth		Holes		Present Status Open or Squeezed	Sacks Cement	Max. Press.	Remarks
	From	To	No.	Size				
0-27-54	3783	3786	18	1/2"	Open			
	3791	3797	36	1/2"	Open			
	3803	3809	36	1/2"	Open			

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUL 13 2007
 CONSERVATION DIVISION
 WICHITA, KS

FORMATION RECORD

Nature of Strata	Color	Top	Bottom	Straight Hole tests	Remarks
Surface clay & sand		0	10		
Sand & shale		10	120		
Sand, shale & shells		120	229		
Shale & shells		229	340		
Shale & sand		340	430		
Shale & sand		430	520	OK	
Shale & shells		520	785		
Sand, shale & red bed		785	1040	OK	
Shale & shells		1040	1370		
Anhydrite		1370	1415		
Red shale & shells		1415	1485	OK	
Shale & shells		1485	1950		
Shale & lime ls		1950	2050	OK	
Shale & Lime		2050	2380		
Lime		2380	2470	OK	
Shale & lime		2470	2865		
Lime		2865	2975	OK	
Lime & shale		2975	3300		
lime & shale		3300	3545		

CONSERVATION DIVISION
WICHITA, KS

JUL 13 2007

RECEIVED
KANSAS CORPORATION COMMISSION

