

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Nadel and Gussman, L.L.C
Address: 15 E. 5th St., Suite 3200, Tulsa, OK 74103
Phone: (918) 583-3333 Operator License #: 32638
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/1/06 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
KC Depth to Top: 3810 Bottom: 3815 T.D. 3815
KC Depth to Top: 3644 Bottom: 3703 T.D. 3703
Arbuckle Depth to Top: 3810 Bottom: 3815 T.D. 3815

API Number: 15-163-03251-00-00
Lease Name: Stithem
Well Number: 17
Spot Location (QQQQ): _____ - NW - NW - NE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 14 Twp. 10S S. R. 20 East West
County: Rooks
Date Well Completed: 7/6/52
Plugging Commenced: 6/7/06
Plugging Completed: 6/7/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KC	Oil	0	160'	10-3/4	160'	none
Arbuckle	Oil	0	3810'	7	3810	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 sks 60/40 poz w/300# hulls down backside. Mixed 135 sks down tbg. Set @ 1600' to circulate. Pulled tbg and put swage on csg and pumped 225 sks poz w/1100# hulls and 100 sks poz w/200# hulls down csg. Max pressure 400#.

Name of Plugging Contractor: Allied Cementing License #: 99996
Address: P.O. Box 31, Russell, KS 67665
Name of Party Responsible for Plugging Fees: Nadel and Gussman, LLC
State of OKLA County, Tulsa, ss.
M.R. Taylor (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 12 2007
CONSERVATION DIVISION
WICHITA, KS

(Signature) M.R. Taylor
(Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 10th day of July, 20 07
Kathy Corron My Commission Expires: 8-1-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]

WELL LOG

NADEL AND GUSMAN

STITHEN WELL No. 17

NW NE 14-10-20W
Rooks County, Kansas

Comm: 6-26-52
Comp: 7-6-52

Casing: 10-3/4" 160' v/100 SAX
7" 3810' v/75 SAX

Formations	Depth
Clay, sand and shale	165
Shale, sand and shells	1674
Anhydrite	1717
Shale, red bed and shells	2065
Shale and broken lime	2260
Lime and shale	2655
Shale and shells	2830
Lime and shale	3527
Lime	3577
Lime and shale	3611
Lime	3717
Conglomerate	3765
Shale	3805
Chert and lime	3812
Lime	3815

GEOLOGICAL TOPS

Heehner Shale	3453
Lansing-K.G.	3490
Conglomerate	3736
Simpson Shale	3789
Arbuckle	3809
Weathered Arb.	3805

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 12 2007

CONSERVATION DIVISION
WICHITA, KS

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

L. C. Hay, of lawful age deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Stithen No. 17 Well in the NW NE 14-10-20W, Rooks County, Kansas.

Subscribed and sworn to before me this 9th day of July, 1952.

L. C. Hay

W. C. [Signature]

Notary Public

My commission expires Nov. 3, 1952

ALLIED CEMENTING CO., INC. 24371

PERMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>6/7/06</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>6:40 p.</u>
LEASE <u>Stithem</u>	WELL # <u>17</u>	LOCATION <u>Palco 3 5 1/2 E</u>			COUNTY <u>Rooks</u>	STATE <u>Ks.</u>	
OLD OR NEW (Circle one) <u>OLD</u>		<u>1/2 5 E into</u>					

CONTRACTOR Alliance Well Service OWNER _____
 TYPE OF JOB Old Hole Plug
 HOLE SIZE _____ T.D. _____
 CASING SIZE 7' DEPTH _____
 TUBING SIZE 2 3/8 DEPTH 1600'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 400 psi MINIMUM —
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

CEMENT
 AMOUNT ORDERED 850 60% 10% Gel
200 Com → used 100 stks
1600 # hulls

COMMON	<u>470</u>	@	<u>1065</u>	<u>5005.50</u>
POZMIX	<u>180</u>	@	<u>580</u>	<u>1044.00</u>
GEL	<u>45</u>	@	<u>1665</u>	<u>749.25</u>
CHLORIDE		@		
ASC		@		
Hulls	<u>16</u>	@	<u>2550</u>	<u>408.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>711</u>	@	<u>190</u>	<u>1350.90</u>
MILEAGE	<u>84/sk/mile</u>			<u>3583.44</u>
TOTAL				<u>12,141.09</u>

EQUIPMENT

PUMP TRUCK CEMENTER Shane
 # 409 HELPER Craig
 BULK TRUCK
 # 410-378 DRIVER Robert, Brian
 BULK TRUCK
 # 396 DRIVER Jody

REMARKS:

Mixed 100stks with 300 #hulls down outside
Mixed 135 stks to Circulate Cement
Put surge on Mixel 225 stks with
1100 # hulls. Mixel 100 stks with
200 # hulls.

SERVICE

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____ 720.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 63 @ 5.00 315.00
 MANIFOLD _____ @ _____
 RECEIVED _____ @ _____
 KANSAS CORPORATION COMMISSION _____ @ _____

JUL 12 2007

TOTAL 1035.00

CONSERVATION DIVISION
WICHITA, KS

PLUG & FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

CHARGE TO: Nadel Gussman
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

thanks

SIGNATURE _____

[Handwritten Signature]

PRINTED NAME _____