

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Raymond Oil Company, Inc.

Address: P.O. Box 48788 Wichita, KS 67201

Phone: (316) 838-7811 Operator License #: 5046

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-185-23425-0000

Lease Name: Gathings

Well Number: 1

Spot Location (OQQQ): NW - NW - SW 2310 Feet from X North / South Section Line

330 Feet from East / X West Section Line

Sec. 18 Twp. 25 S. R. 11 East X West

County: Stafford

Date Well Completed:

Plugging Commenced: 6-28-07

Plugging Completed: 7-2-07

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten data for casing sizes 8 5/8" and 5 1/2" and depths 263' and 4182'.

RECEIVED JUL 16 2007 KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Found bottom @ 4130' & Sanded. Popped 5 1/2 casing slips, stretched casing, gained 23".

Checked hole, found sand at 3920', dumped 5sx. cement. Cut casing loose @ 2425', pulled 1800' of casing, stopping @ 625'. Pumped 50sx. cement @ 625', pulled 325' of 5 1/2 casing, stopping @ 300'. Pumped 50sx., pulled 300' out & ran 40' back in hole. Pumped 30sx. cement, circulated top.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Raymond Oil Company, Inc.

State of Kansas County: Rice ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 11th day of July, 2007

[Handwritten Signature] My Commission Expires: Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]