

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kerr-McGee Oil & Gas Onshore LP

Address: P. O. Box 1330

Phone: 832-636-8380 Operator License #: 33002

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04/09/2007 (Date)

by: Barry Metz (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Herrington Depth to Top: 2638 Bottom: 2698 T.D. 2767

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15- 081-00187 -00-00

Lease Name: McConnell

Well Number: 1

Spot Location (QQQQ): NE - NE - NE - SW

2490 Feet from North / South Section Line

2490 Feet from East / West Section Line

Sec. 17 Twp. 28 S. R. 32 East West

County: Haskell

Date Well Completed: 03/1953

Plugging Commenced: 05/29/07

Plugging Completed: 06/04/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		Surface	600'	8-5/8"	600'	0
Herrington	Gas	Surface	2699'	5-1/2"	2699'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

Pull 88 jts 1-1/4" tbg. Stung out of 3-1/2" pkr, pulled 1 jt. Mixed 100 lb hulls & 20 sks cmt to plug to 2540'.

Pulled rest of 3-1/2" tbg. Mixed 20 sk plug from 900' to 740'. Mixed 70 sk plug from 600' to 0'. Mixed 10 sks down annulus from 60' to 0'. Cut off 8-5/8" & 5-1/2" csg. Capped 8-5/8" csg 3' below gr. level.

Name of Plugging Contractor: Sargent & Horton Plugging, Inc License #: 31151

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Kerr-McGee Oil & Gas Onshore LP

State of Texas County, Montgomery, ss.

Diana Smart (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) 1201 Lake Robbins Dr The Woodlands, TX 77380

SUBSCRIBED and SWORN TO before me this 11th day of July, 2007

Bertha Nefe
Notary Public My Commission Expires: 12-27-09



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 16 2007

CONSERVATION DIVISION

Handwritten initials/signature