

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: George Rice, dba Rice Production Company  
Address: 1219 Random Road, Hoisington, Ks. 67544  
Phone: (620) 653-4979 Operator License #: 31154  
Type of Well: Oil DH KCC Pkt 7/20/07 per CP2/3 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: July 3, 2007 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Topeka Depth to Top: 2780 Bottom: 3057 T.D. \_\_\_\_\_  
Lansing Kansas City Depth to Top: 3157 Bottom: 3378 T.D. \_\_\_\_\_  
Arbuckle Depth to Top: 3390 Bottom: 3417 T.D. 3417

API Number: 15 - 009250700000  
Lease Name: Oltmann  
Well Number: 8  
Spot Location (QQQQ): C - s/2 - nw - SW  
1675' Feet from  North /  South Section Line  
660' Feet from  East /  West Section Line  
Sec. 15 Twp. 1718' S. R. 13  East  West  
County: Barton  
Date Well Completed: July 3, 2007  
Plugging Commenced: July 3, 2007  
Plugging Completed: July 3, 2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled Out
Topeka	water/oil	0'	459'	8 5/8'	459'	none
Lansing Kansas city	water/oil					
Arbuckle	water/oil					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 4 1/2" drill pipe in open hole to 3365', spot 25 sx cement, 60/40 w/ 6% gel. Pull up to 856' and spot 25 sx cement. Pull up to 509' spot 90 sx cement. Pull to 40' spot 10sx cement. Plug rat hole with 15 sx cement and 10 sx cement to mouse hole.

Name of Plugging Contractor: Warren Drilling License #: 33724  
Address: 7570 West 21st Street North Bldg #1050 Ste.C, Wichita, Ks. 67205


Name of Party Responsible for Plugging Fees: George Rice dba Rice Production Co.

State of KANSAS County, BARTON, ss.

GEORGE RICE (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 17 day of July, 2007



Julie A. Heine My Commission Expires: 2-6-2008  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUL 18 2007  
CONSERVATION DIVISION  
WICHITA, KS