

MAY 21 2007

CONSERVATION DIVISION
WICHITA, KS

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 189-20491 -60-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date spud 5/15/80

Well Operator: XTO Energy, Inc KCC License #: 32864
(Owner / Company Name) (Operator's)

Address: 210 Park Ave., Ste. 2350 City: Oklahoma City

State: OK Zip Code: 73102 Contact Phone: (405) 319-3212

Lease: Mahoney Well #: 1-2 Sec. 2 Twp. 35 S. R. 35 East West

C - NW Spot Location / QQQQ County: Stevens

1320' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 13 3/8" Set at: 698' Cemented with: 350 Sacks

Surface Casing Size: 8 5/8" Set at: 2850' Cemented with: 600 Sacks

Production Casing Size: 4 1/2" Set at: 6748' Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: 6520' - 6534', 6294' - 6310', 6233' - 6237' CIBP @ 6500'

Elevation: 2970' (G.L. / K.B.) T.D.: 6750 PBTD: 6490 Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 60' cement plug 6230' - 6290', 60' cement plug 6170' - 6230',

cut off casing @ +/- 5300', 110' plug 2800' - 2910', 110' in & out cement plug 640' - 760', in & out cement plug from 4' - 30', weld on marker

all intervals between cement plugs will be filled with mud.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lonnie Tarvin

Phone: (580) 651-7361

Address: P. O. Box 209 City / State: Tyrone, OK 73951

Plugging Contractor: Not selected at this time Bloomer Well Service KCC License #: 5353
(Company Name) (Contractor's)

Address: 2926 Vermont Rd Rantoul, ks 66079 Phone: (785) 878-3497

Proposed Date and Hour of Plugging (if known?): Not known at this time

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/16/07 Authorized Operator / Agent: Karen Byers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

XTO ENERGY INC.
210 PARK AVENUE - SUITE 2350
OKLAHOMA CITY, OK 73102

June 07, 2007

Re: MAHONEY #1-2
API 15-189-20491-00-00
2-35S-35W, 1320 FNL 1320 FWL
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888