

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

MAY 29 2007

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Renick Energy, L.C.

Address: 10502 6 Road Ingalls KS 67853

Phone: (620) 335-5172 Operator License: 33358

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: February 12, 2007 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Mississippi Depth to Top: 4896 Bottom: 5016 T.D. 5060
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-069-20-111-000

Lease Name: Renick

Well Number: 3 KCC Per CP2/S

Spot Location (QQQQ): SWNWSE

700 Feet from North / South Section Line

2570 Feet from East / West Section Line

Sec. 22 Twp. 25 S. R. 30 East West

County: Gray

Date Well Completed: _____

Plugging Commenced: 4-26-07

Plugging Completed: 4-26-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	850	8 5/8	850	0
		0	5042	4 1/2	5042	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 950' with 2 sacks cement on top. Perforate 4 holes at 870". Set cement retainer at 820".

Pump 150 sx 60/40 6% gel up 4 1/2 x 8 5/8 annulus. Fill 4 1/2 csg from 820' to 0' with 50 sx. Pump 50 sx down 4 1/2 x 8 5/8 annulus.

Plugging complete

Name of Plugging Contractor: Allied Cementing License #: 99996

Address: P.O. Box 31 Russell KS 67665

Name of Party Responsible for Plugging Fees: Mark Renick

State of Kansas County, Gray, ss.

Mark Renick

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Renick

(Address) 10502 6 Road Ingalls KS 67853

SUBSCRIBED and SWORN TO before me this 25th day of May, 2007

AMBER R. HARMON
Notary Public - State of Kansas
My Appt. Expires 8/23/07

Amber R. Harmon
Notary Public

My Commission Expires: 8/23/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC
PKT
10/10/07
P21
RBDNS

02