

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JUN 05 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: PETROHAWK OPERATING COMPANY

Address: 4975 PRESTON PARK BLVD #320 WEST TOWER

Phone: (972) 767-1291 Operator License #: 32832

Type of Well: GAS SWD per RBDns Docket #: D24422
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 01/18/2006 & 05/02/2007 (Date)

by: STEVE DURANT (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

COUNCIL GROVE Depth to Top: 2873 Bottom: 2938 T.D. 65

LANSING Depth to Top: 4146 Bottom: 4190 T.D. 44

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-093-20820-00-00

Lease Name: REXFORD *KCC PKT*

Well Number: #1 *6/12/07 perc 2/3*

Spot Location (QQQQ): SW4 *nenesws*

1250 Feet from North / South Section Line

1250 Feet from East / West Section Line

Sec. 22 Twp. 23S S. R. 38 East West

County: KEARNY

Date Well Completed: 10/05/1985

Plugging Commenced: 05/14/2007

Plugging Completed: 05/14/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2873	2938	SURF 8-5/8	1852	NONE
LANSING	SWD	4146	4190	PROD 5-1/2	4231	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET CIBP IN 5-1/2" @4000; DUMP 2 SX CEMENT ON TOP

SET CIBP IN 5-1/2" @2700

SET CIBP @950; PERFORATE @900

MIX 250 SX, 60/40 POZ 6% GEL; CIRC UP BACKSIDE TO SURFACE.

Name of Plugging Contractor: POST & MARTIN WELL SERVICE License #: 8438

Address: BOX 297, GARDEN CITY, KS 67846

Name of Party Responsible for Plugging Fees: PETROHAWK OPERATING COMPANY


State of TEXAS County, HARRIS, ss.

CORINNE ILLICH (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Corinne Illich*

(Address) 4975 PRESTON PARK BLVD, #320-WEST TOWER, PLANO TX 75093



SUBSCRIBED and SWORN TO before me this 4TH day of JUNE, 20 07

Kimberly A Gafford My Commission Expires: May 16, 2010
Notary Public

PKT