

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED KANSAS CORPORATION COMMISSION

JUN 05 2007

Form CP-4 December 2003

CONSERVATION DIVISION WICHITA, KS

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Stelbar Oil Corporation, Inc.

Address: 1625 North Waterfront Parkway, Suite 200 Wichita, KS 67206

Phone: (316) 264-8378 Operator License #: 6044

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04/16/07 (Date)

by: Duane Kruger (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Bartlesville Depth to Top: 2,838' Bottom: 2,860' T.D. 2,918'

API Number: 15-015-22267-00-00

Lease Name: E. B. Shawver

Well Number: 9-27

Spot Location (QQQQ): S2-SE-SE-SE 80 Feet from North South Section Line

330 Feet from East West Section Line

Sec. 27 Twp. 29 S. R. 4 East West

County: Butler

Date Well Completed: 03/15/1983

Plugging Commenced: 04/17/07

Plugging Completed: 04/19/07

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Bartlesville and 2,838' to 2,860'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CIBP at 2,817'. Dump 5 sacks cement on CIBP. Shoot off casing at 841'. POOH with casing. RIH with 2-3/8" tubing to 310'.

Establish circulation. Mix and pump 112 sacks cement and circulate cement from 310' to surface. POOH with tubing.

All cement was 60/40 pozmix with 4% gel.

Name of Plugging Contractor: Stelbar Oil Corporation, Inc. License #: 6044

Address: 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206

Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.

State of Kansas County, Sedgwick, ss.

Roscoe L. Mendenhall (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roscoe L. Mendenhall

(Address) 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206

NANCY N. PRUITT Notary Public - State of Kansas My Appt. Expires 06-11-09

SUBSCRIBED and SWORN TO before me this 4th day of June, 2007

(Signature) Nancy N. Pruitt Notary Public My Commission Expires: June 11, 2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



**CONSOLIDATED**  
OIL WELL  
SERVICES, LLC

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 1228  
Denver, CO 80256

**MAIN OFFICE**  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 213185

Invoice Date: 04/26/2007 Terms: Page 1

STELBAR OIL CORP., INC.  
SUITE 200  
1625 N. WATERFRONT PARKWAY  
WICHITA KS 67206-6602  
(316)264-8378

S.W.M.C. 9-27  
17043  
04-19-07

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	112.00	9.8000	1097.60
1118A	S-5 GEL/ BENTONITE (50#)	450.00	.1500	67.50

Description	Hours	Unit Price	Total
434 80 BBL VACUUM TRUCK (CEMENT)	3.00	90.00	270.00
446 P & A OLD WELL	1.00	550.00	550.00
446 EQUIPMENT MILEAGE (ONE WAY)	30.00	3.30	99.00
491 MIN. BULK DELIVERY	1.00	285.00	285.00

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 05 2007

CONSERVATION DIVISION  
WICHITA, KS

Parts:	1165.10	Freight:	.00	Tax:	61.75	AR	2430.85
Labor:	.00	Misc:	.00	Total:	2430.85		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

BARTLESVILLE, OK  
278 CR 2706 74003  
918/338-0808

EUREKA, KS  
820 E. 7th 67045  
620/583-7664

OTTAWA, KS  
2631 So. Eisenhower Ave. 66087  
785/242-4044

GILLETTE, WY  
300 Enterprise Avenue 82716  
307/686-4914

THAYER, KS  
8655 Dorn Road 66776  
620/839-5269

WORLAND, WY  
837 Hwy US 16 E 82401  
307/347-4577

CONSOLIDATED OIL WELL SERVICES, LLC  
 P.O. BOX 884, CHANUTE, KS 66720  
 620-431-9210 OR 800-467-8676

TICKET NUMBER 17043  
 LOCATION El Dorado  
 FOREMAN Jim Thomas

TREATMENT REPORT & FIELD TICKET  
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-19-07	7396	S.W.M.C # 9-27	27	29	4E	Butler
CUSTOMER Stelbar Oil Corp.			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 155 Market St Suite 500			446	Jacob		
CITY STATE ZIP CODE Wichita Ks 67202			491	Tobb		
			434	Jeff		

JOB TYPE Plug HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2"  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 7/8" OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting Ran 2 7/8" tubing to 310ft. Brake circulation. Mix & pump 1125ks 60/40 po2 4% gel to surface. cement circulated in the cellar.

RECEIVED  
 KANSAS CORPORATION COMMISSION

JUN 05 2007

CONSERVATION DIVISION  
 WICHITA, KS

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	550.00	550.00
5406	30	MILEAGE	3.30	99.00
1131	1125ks	60/40 po2 4% gel	9.70	1091.60
118A	450lbs	4% gel	.15	67.50
5502C	3hrs	80 BDL Vlc	90.00	270.00
5407A	1	min Dulk Charge	215.00	215.00
Subtotal				2088.10
			SALES TAX	61.75
			ESTIMATED TOTAL	2149.85

213185

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_