

JUN 05 2007

Form CP-4  
December 2003

CONSERVATION DIVISION  
WICHITA, KS  
Type or Print on this Form  
Form must be Signed  
Blanks must be Filled

**Notice:** Fill out COMPLETELY  
at return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Lease Operator: Stelbar Oil Corporation, Inc.  
Address: 1625 North Waterfront Parkway, Suite 200 Wichita, KS 67206  
Phone: (316) 264-8378 Operator License #: 6044  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 04/09/07 (Date)  
by: Duane Kruger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Bartlesville Depth to Top: 2,852' Bottom: 2,864' T.D. 2,947'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 015- 23586 -00-00  
Lease Name: Muddy Creek Southwest Unit  
Well Number: 12  
Spot Location (QQQQ): \_\_\_\_\_ - SE - SW - SW  
330 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 26 Twp. 29 S. R. 4  East  West  
County: Butler  
Date Well Completed: 01/09/2001  
Plugging Commenced: 04/10/07  
Plugging Completed: 04/11/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bartlesville	oil and saltwater	Surface	269'	8-5/8"	269'	None
2,852' to 2,864'		Surface	2,947'	5-1/2"	2,947'	1,405'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2,813'. Dump 5 sacks cement on CIBP. Shoot off casing at 1,405'. POOH with casing. RIH with 2-3/8" tubing to 330'.  
Establish circulation. Mix and pump 110 sacks cement and circulate cement from 330' to surface. POOH with tubing.  
All cement was 60/40 pozmix with 4% gel.


Name of Plugging Contractor: Stelbar Oil Corporation, Inc. License #: 6044  
Address: 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206

Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.  
State of Kansas County, Sedgwick, ss.

Roscoe L. Mendenhall  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roscoe L. Mendenhall

(Address) 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206



SUBSCRIBED and SWORN TO before me this 4th day of June, 20 07

Nancy N. Pruitt  
Notary Public My Commission Expires: June 11, 2009

*PKT*

**CONSOLIDATED**  
OIL WELL  
SERVICES, LLC

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 1228  
Denver, CO 80256

**MAIN OFFICE**  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 212914

Invoice Date: 04/12/2007 Terms:

Page 1

STELBAR OIL CORP., INC.  
SUITE 200  
1625 N. WATERFRONT PARKWAY  
WICHITA KS 67206-6602  
(316)264-8378

S.W.M.C. #12  
17038  
04-11-07

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	110.00	9.8000	1078.00
1118A	S-5 GEL/ BENTONITE (50#)	450.00	.1500	67.50
1123	CITY WATER	3000.00	.0128	38.40

Description	Hours	Unit Price	Total
446 P & A OLD WELL	1.00	550.00	550.00
446 EQUIPMENT MILEAGE (ONE WAY)	30.00	3.30	99.00
436 80 BBL VACUUM TRUCK (CEMENT)	3.00	90.00	270.00
515 MIN. BULK DELIVERY	1.00	285.00	285.00

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 15 2007

CONSERVATION DIVISION  
WICHITA, KS

Parts:	1183.90	Freight:	.00	Tax:	62.75	AR	2450.65
Labor:	.00	Misc:	.00	Total:	2450.65		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

BARTLESVILLE, OK  
278 CR 2706 74003  
918/338-0808

EUREKA, KS  
820 E. 7th 67045  
620/583-7664

OTTAWA, KS  
2631 So. Eisenhower Ave. 66067  
785/242-4044

GILLETTE, WY  
300 Enterprise Avenue 82716  
307/686-4914

THAYER, KS  
8655 Dorn Road 66776  
620/839-5269

WORLAND, WY  
837 Hwy US 16 E 82401  
307/347-4577

CONSOLIDATED OIL WELL SERVICES, LLC

P.O. BOX 884, CHANUTE, KS 66720

620-431-9210 OR 800-467-8676

TICKET NUMBER 17038

LOCATION F/Danada 780

FOREMAN Jim Thomas

TREATMENT REPORT & FIELD TICKET  
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-11-07	7396	S.W.M.C. # 12	26	29	4E	Dutler
CUSTOMER Stelbar Oil Corp			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 155 N. Market St. Suite 500			446	Jacob		
CITY STATE ZIP CODE Wichita Ks 67202			515	Colin		
			436	JP		

JOB TYPE Plug HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2"  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 7/8" OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Softy Meeting Ran 2 7/8" tubing to 330ft. Brake circulation, Mix & pump 110SKs to surface. Cement circulated in the collar.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 05 2007

CONSERVATION DIVISION  
WICHITA, KS

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A .80	1	PUMP CHARGE	550.00	550.00
5406 .80	30	MILEAGE	3.30	99.00
1131 .80	110 SKs	60/40 Poz mix 4% gel	9.80	1078.00
1118A .80	450 lbs	4% gel	.15	67.50
1123 .80	3000 gal	City Water	12.80	38.40
5502C .70	3 hrs	80 BBL Vac	90.00	270.00
5407 .70	1	min. Dulk Charge	255.00	255.00
Subtotal				2381.90
5.2%			SALES TAX	124.15
ESTIMATED TOTAL				2450.65

012914 / 012915

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_