

STATE OF KANSAS
COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-079-20587 -00-00
LEASE NAME Pizinger
WELL NUMBER 3

RECEIVED
FEB 19 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR HOWELL OIL COMPANY, INC.
ADDRESS 1000 West Lois Lane Bella Vista, AR. 72715
PHONE (479) 876-6842 OPERATORS LICENSE NO. 5091
Character of Well Oil

3960 Ft. from S Section Line
4290 Ft. from E Section Line
SEC. 18 TWP. 23 RGE. 3W (E) or (W)
COUNTY Harvey
Date Well Completed 10-20-1984
Plugging Commenced 1-29-04 2-03-04
Plugging Completed 2-4-04 2-03-04

Character of Well (Oil, Gas, D&A, SWD, Input, Water Supply Well)
A plugging proposal was approved on _____ (date)
Jack Luthi (KCC District Agent's Name).

ACG-1 filed? _____ If not, is well log attached? _____
Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3425'
Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>			<u>289</u>	<u>10-3/4"</u>	<u>287'</u>	<u>None</u>
<u>Prod</u>			<u>3424</u>	<u>5-1/2"</u>	<u>3424'</u>	<u>1028'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side.
Plugged off bottom with sand to 3310' and 5 sacks cement. Cut 5-1/2" casing loose @1028', pulled up to 550', pumped 35 sacks 2%cc cement, pulled up to 350' and circulated cement to surface. Used 60/40 pos. 6% gel. Topped off with 11 sacks cement. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529
Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Howell Oil Company, Inc.
STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of February, 2004
[Signature]
Notary Public

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05
Form CP Revised 05-