

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chesapeake Operating, Inc.
Address: P.O., Box 18496, Oklahoma City, OK 73154-0496
Phone: (405) 879-9375 Operator License #: 32334
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/9/2007 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5,295' Bottom: 5,304' T.D. 5,700'
Chester Depth to Top: 5,476' Bottom: 5,481' T.D. 5,700'
St. Genevieve Depth to Top: 5,631' Bottom: 5,638' T.D. 5,700'

API Number: 15 - 081-20899 - 00 - 01
Lease Name: MLP Rooney
Well Number: 1-5
Spot Location (QQQQ): _____ - C - NE - SE
1980 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 5th Twp. 30S S. R. 34S East West
County: Haskell
Date Well Completed: 2/16/1999
Plugging Commenced: 6/1/07
Plugging Completed: 6/1/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow		Surface	1,855'	8 5/8"	1,805'	
Chester		Surface	5,690'	5 1/2"	5,728'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Set CIBP at 5,250', spot 2 sx of cmt on plug. Cut off 5 1/2" casing at 1,771'. Spot 50 sx of cmt from 1,620' - 1,770'. Spot 40 sx from 540' - 660'. Spot 10 sx from 40' to surface. Cut off 8 5/8" 4' below ground level and weld on plate.

Name of Plugging Contractor: Sargents & Horton Plugging License #: _____
Address: R.R. #1, Box 49BA, Tyrone, OK 73951

Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.
State of Oklahoma County, Oklahoma, ss. _____

Doug Howeth, Associate Asset Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Aletha Double-King For Doug Howeth Assoc. Asset Mgr.
(Address) P.O. Box 18496, Oklahoma City, OK 73154-0496



SWORN TO before me this 5th day of June, 20 07
My Commission Expires: 10/22/07
Comm. # 99017390

Handwritten initials