

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 5/22/07 (Date)  
by: Mike Meirs (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 4574 Bottom: 4646 T.D. 4646  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-135-23,374-00-00  
Lease Name: Bentley  
Well Number: #1-16  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - NE  
4950 Feet from  North /  South Section Line  
230 Feet from  East /  West Section Line  
Sec. 16 Twp. 18S S. R. 26  East  West  
County: Ness  
Date Well Completed: 10/28/89  
Plugging Commenced: 5/22/07  
Plugging Completed: 5/23/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	slight oil	0'	207'	8-5/8"	207'	0'
	saltwater	0'	4641'	5-1/2"	4641'	0'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Retreived the RBP & pulled out of hole w/ all tools. Go back in hole w/ open ended tbg to 4520'. Dug out the bradenhead and filled w/30 sx cmt & tested to 500 psi. Mix & spot 30 sx of cmt w/2 sx of hulls on btm. Pull tbg up to 2000'. Swift Serv. mixed & pumped 192 sx cmt w/8 sx of hulls. Lost circ. at 170 sx in. Pull tbg out of hole. Went in hole with open ended tbg and tagged cmt @ 1150'. Pick up to one jt. Swift Serv. mixed & pumped 90 sx of cmt and got returns to surf. Pulled tbg out of hole. Top off 5 1/2" csg w/10 sx cmt. KCC rep, Mike Meirs, witnessed plugging.

Name of Plugging Contractor: North Fork Well Service LLC License #: 32382 32938  
Address: P.O. Box 466, Ness City, KS 67560-0466  
Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss. \_\_\_\_\_  
Lanny Butner (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Lanny Butner  
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 4th day of June  
Michelle D. Henning My Commission Expires \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PKT*