

JUN 05 2007

Form CP-4
December 2003

Type or Print on this Form
CONSERVATION DIVISION Form must be Signed
WICHITA, KS All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Lease Operator: Stelbar Oil Corporation, Inc.

Address: 1625 North Waterfront Parkway, Suite 200 Wichita, KS 67206

Phone: (316) 264-8378 Operator License #: 6044

Type of Well: Water Injection Well EOR Docket #: E-24961
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04/10/07 (Date)

by: Duane Kruger (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Bartlesville Depth to Top: 2,836' Bottom: 2,857' T.D. 2,937'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-015-21940-00-01
Lease Name: E.B. Shawver EBS II
Well Number: 4-26
Spot Location (QQQQ): ~~W~~ - SE - SW - NW
2,910 Feet from North / South Section Line
4,450 Feet from East / West Section Line
Sec. 26 Twp. 29 S. R. 4 East West
County: Butler
Date Well Completed: 01/29/1982
Plugging Commenced: 04/11/07
Plugging Completed: 04/16/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bartlesville	oil and saltwater	Surface	248'	8-5/8"	248'	None
2,836' to 2,857'		Surface	2,937'	5-1/2"	2,937'	1,409'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2,788'. Dump 5 sacks cement on CIBP. Shoot off casing at 1,409'. POOH with casing. RIH with 2-3/8" tubing to 300'.
Establish circulation. Mix and pump 108 sacks cement and circulate cement from 300' to surface. POOH with tubing.
All cement was 60/40 pozmix with 4% gel.

Name of Plugging Contractor: Stelbar Oil Corporation, Inc. License #: 6044

Address: 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206

Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.

State of Kansas County, Sedgwick, ss.

Roscoe L. Mendenhall (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NANCY N. PRUITT
Notary Public - State of Kansas
My Appt. Expires 06-11-09

(Signature) Roscoe L. Mendenhall
(Address) 1625 North Waterfront Parkway, Suite 200 Wichita, Kansas 67206

SUBSCRIBED and SWORN TO before me this 4th day of June, 20 07

Nancy N. Pruitt My Commission Expires: June 11, 2009
Notary Public

CONSOLIDATED
OIL WELL
SERVICES, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 1228
Denver, CO 80256

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE Invoice # 213076

Invoice Date: 04/23/2007 Terms: Page 1

STELBAR OIL CORP., INC.
SUITE 200
1625 N. WATERFRONT PARKWAY
WICHITA KS 67206-6602
(316)264-8378

E.B. SHAWLER 4-26
17175
04-16-07

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	108.00	9.8000	1058.40
1118A	S-5 GEL/ BENTONITE (50#)	400.00	.1500	60.00
1123	CITY WATER	3000.00	.0128	38.40

Description	Hours	Unit Price	Total
434 80 BBL VACUUM TRUCK (CEMENT)	3.00	90.00	270.00
467 P & A OLD WELL	1.00	550.00	550.00
467 EQUIPMENT MILEAGE (ONE WAY)	28.00	3.30	92.40
491 MIN. BULK DELIVERY	1.00	285.00	285.00

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 05 2007

CONSERVATION DIVISION
WICHITA, KS

Sumc
353
Bon

Parts:	1156.80	Freight:	.00	Tax:	61.32	AR	2415.52
Labor:	.00	Misc:	.00	Total:	2415.52		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____

CONSOLIDATED OIL WELL SERVICES, *LLC*
 P.O. BOX 884, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

TICKET NUMBER 17175
 LOCATION Eldorado #80
 FOREMAN Larry Stearns

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-16-07	7396	E.B. Shawyer 4-216	216	29S	4E	Rush
CUSTOMER <i>Stelbar Oil Co.</i>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <i>155 W. Market St. Suite 500</i>			<i>467</i>	<i>Shawn</i>		
CITY <i>Wichita</i>			<i>491</i>	<i>LOD</i>		
STATE <i>Ks</i>			<i>434</i>	<i>Jeff</i>		
ZIP CODE <i>67202</i>						

JOB TYPE Plug HOLE SIZE 7 7/8 HOLE DEPTH _____ CASING SIZE & WEIGHT 8 3/4 23#
 CASING DEPTH 248 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 300 to Junction
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: *Safety meeting - Hooked up to 2 3/8 tubing - Took 2 1/2 bbls to
 Break Great Artesian IMP with 108 lbs 60/40 Poz-mix + 4% Gel of
 Circulate Cement to Surface. Pulled tubing - hole standing full.*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A		PUMP CHARGE	550.00	550.00
5406	28	MILEAGE	3.30	92.40
1131	108	60/40 Poz-mix	9.80	1058.40
1118A	400#	Gel	.15	60.00
5502C	3 hrs	80 bbl Vac. Truck	90.00	270.00
1123	3000 gals	City water	12.80	38.40
5407	1	Mens Bulk Charge	285.00	285.00
RECEIVED KANSAS CORPORATION COMMISSION				
JUN 05 2007				
CONSERVATION DIVISION WICHITA, KS				
Subtotal				2354.20
			5.390	SALES TAX
				ESTIMATED TOTAL
				2415.52

AUTHORIZATION _____ TITLE _____ DATE _____