

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation  
Address: 100 S. Main, Suite 200, Wichita, KS 67202  
Phone: (316) 262-3596 Operator License #: 9408  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 5/29/07 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing/KC Depth to Top: 3332' Bottom: 3493' T.D. \_\_\_\_\_  
Arbuckle Depth to Top: 3655' Bottom: 3670' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-21,933 - 00-00  
Lease Name: Gladys  
Well Number: 5  
Spot Location (QQQQ): N2 - SW - NW -  
1650 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 12 Twp. 11 S. R. 19  East  West  
County: Ellis  
Date Well Completed: 1980  
Plugging Commenced: 5/29/07  
Plugging Completed: 5/29/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	170'	8-5/8"		
		Surface	3695'	4-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PLUG AND ABANDON. Express Well Serv MIRU.Perf Tech perf @2025,1450,750,150 w/2 shts ea. Run tbg to 2138'. Swift Cementing #4751.  
230 sxs @ 2138,6bags hulls.110 sxs @1700 w/5 sxs hulls.110 sxs. Pull tbg to750'. Mix 5 sxs SMD dn tbg.Cement circulates.  
Pull tbg mix 5 sxs and pressure to 400# holding ok. 5 sx dn annulus. Pat Staab w/KCC. 450 sxs 60/40 Poxmix 10% gel plus 15 sxs SMD used.

Name of Plugging Contractor: Express Well Service License #: 6426 **RECEIVED KANSAS CORPORATION COMMISSION**  
Address: P.O. Box 19, Victoria, KS 67671-0019 **JUN 11 2007**  
Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation **CONSERVATION DIVISION WICHITA, KS**  
State of Kansas County, Sedgwick, ss.  
Gary Sharp

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp  
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 7th day of June 20 07  
Glenna E. Lowe My Commission Expires: \_\_\_\_\_  
Notary Public

**GLENN E. LOWE**  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 12-2-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202