

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed**  
**Form must be Signed**  
**All blanks must be Filled**

API # 15 - 051-30683-00012 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1970.

Well Operator: The Bill Bowman Oil Company (Owner / Company Name) KCC License #: 33263 (Operator's)

Address: 2640 W Road City: Natoma

State: Kansas Zip Code: 67651 Contact Phone: (785 ) 885 - 4830

Lease: Peavey (Jacobs-Peavey) Well #: 4 Sec. 26 Twp. 11 S. R. 18  East  West

- NE - NE - SW Spot Location / QQQQ County: Ellis

2310 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # D 15,759  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 1339 Cemented with: unknown - circ. to govt. Sacks

Production Casing Size: 5 1/2 Set at: 3721 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 905 - 1045

Elevation: 2108 ( G.L. /  K.B.) T.D.: 3721 PBTD: 1140 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): According to KCC District # 4 rules and regulations

**RECEIVED**  
**JUN 18 2007**  
**KCC WICHITA**

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Scient records.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: William F Bowman

Phone: (785 ) 885 - 4830

Address: 2640 W Road City / State: Natoma, KS 67651

Plugging Contractor: Allied Cementing (Company Name) KCC License #: 99996 (Contractor's)

Address: Russell, KS Phone: (785 ) 483 - 2627

Proposed Date and Hour of Plugging (if known?): by July 1, 2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent


Date: July 26, 2006 Authorized Operator / Agent: William F. Bowman (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MURFIN DRILLING CO. #4 "OWWO" 26-11-18W  
 WICHITA, KANSAS JACOBS-PEAVEY NE NE SW  
 CONTR MURFIN DRILLING CTY ELLIS

GEOL FIELD BEMIS-SHUTTS

E 2108 RB CM CARD ISSUED 7/23/70 IP P 25 BO + WTR  
 LANS 3372-3574 &  
 SWDW/ARB 3721-4041



SCH LOGTOPS	DEPTH	DATUM
HEEB	3324	-1216
TOR	3348	-1240
LANS	3370	-1262
CONG	3630	-1522
SIMP	3638	-1530
ARB	3661	-1553
TD	3713	-1605
DDTD	4041	-1933

API  
 OLD INFO: WAS BAY PET. #1 JACOBS D&A/  
 12/12/47; 8" 1339  
 DST(1) 3664-72/25", 10' M  
 NEW INFO: 5 1/2" 3721/175SX  
 DST(1) 3672-3700/20-20-20-20, 1830' MW,  
 BHP 1090-934#, FP 56-837#  
 CO & PF 3372-75, 3388-90, 3406-09, 3412-  
 15, 3447-57, 3530-40, 3549-51, 3570-74  
 PB 3600 PKR @ 3315 250MA + 1000 RETARDED  
 + 1000 ACID SWB LD & SWB 2-3BF/SC OIL  
 RE-SET PLUF 3470 PKR @ 3426 250 MA +  
 1500 AC COMM SWB LD & SWB 7BFPH 2% OIL  
 RE-SET PKR @ 3365 250 MA + 3000 RETARDED  
 PLUG AT 3600 ALL ZONES COMM. 5300 GALS  
 ACID SWB LD & SWB 27BFPH 15% OIL/12HRS  
 TO BE LANS-KC WELL & ARB DISP, POP

CORRECTED CARD: 7/30/70

WAS: 26-11-19W  
 IS: 26-11-18W

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 JUN 18 2007  
 KCC WICHITA

4-050126

12-17<sup>th</sup> 015,759  
Amendment

TO:

API number: 15- - 48189

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SW /4 SEC. 26, 11 S, 18 W  
2310 feet from S section line  
2970 feet from E section line

RECEIVED

JUN 18 2007

Operator license# 7377

Lease JACOBS-PEAVEY well# 4

KCC WICHITA

Operator: JOE F. MEIER OIL OPERATIONS County ELLIS

Address: P.O. BOX 871

Well total depth 3721 feet

HAYS, KANSAS 67601

Conductor Pipe: \_\_\_\_\_ inch @ \_\_\_\_\_ feet

913-625-9525

Surface Pipe: 8 5/8 inch @ 1389 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD X, D & A \_\_\_\_\_

Plugging contractor: B.J. SERVICES License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: PM Day: 16 Month: DECEMBER Year: 1991

Plugging proposal received from: JOE F. MEIER

Company: JOE F. MEIER OIL OPERATIONS phone: 913-625-9525

Were: ORDERED 400 SACKS 65/35 POZ-MIX 6% GEL AND 225 SACKS COMMON CEMENT TO PLUG DEEP SWD BACK TO CEDAR-HILLS SWD.

WELL RECORD: 8 5/8" CSG. @1389' CEMENT CIRCULATED TO SURFACE

5 1/2" CSG. @3722' W/175 SACKS CEMENT

CEMENT FROM 3721 TO 1140. PERFORATE AT 1100 AND CIRCULATE CEMENT TO SURFACE.

DEC 23 1991

Plugging Proposal Received by: MARVIN L. MILLER

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 3:15 PM, Day: 17, Month: DECEMBER, Year: 1991

Actual plugging report: (12/13/91) RAN TBG. TO 3708 PUMPED 75 SKS. COMMON CMT. PULLED TBG. TO 3012 PUMPED 200 SKS. 65/35 POZ 6% GEL PULLED TBG. TO 1122 CIRCULATED HOLE CLEAN. (12/16/91) RAN TBG. TO 1825 TAGGED CMT PUMPED 100 SKS. COMMON CMT. PULLED TGB. LET SET 2 HRS. PRESSURED UP CSG. HELD AT 500 PSI. (12/17/91) RAN TBG. BACK TO 950 CMT TOP DRILLED OUT FROM 950 TO 1107 PERFORATED @ 1100' PUMPED 160 SKS. 65/35 POZ 6% GEL AND 50 SKS. COMMON CMT. CIRCULATED CMT TO SURFACE APPROX 50-75 SKS. TO PIT. PUSHED WIRELINE PLUG TO 1060'.

Remarks: MARVIN MILLER WITNESSED 12/13 & 16, HERB DEINES WITNESSED 12/17 PLUGGING.

I did[XX] / did not[ ] observe the plugging.

*Herb Deines*

*Marvin L. Miller*  
Marvin L. Miller



CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

BOWMAN, WILLIAM F. DBA THE BILL BOWMAN OIL CO  
2640 W ROAD  
NATOMA, KS 67651

June 19, 2007

Re: JACOBS-PEAVEY #4  
API 15-051-30683-00-02  
26-11S-18W, 2310 FSL 2970 FEL  
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Steve Bond  
Production Department Supervisor

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550