

Operator Name: DOWNING-NELSON OIL CO., INC. Lease Name: HONAS Well #: 1-29
 Sec. 29 Twp. 13 S. R. 21W East West County: Trego

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

CNL/GR, DIL, Microlog, Sonic

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Top Anhy.	1772	+594
Base Anhy.	1816	+550
Topeka	3455	-1089
Heebner	3686	-1320
Toronto	3705	-1339
LKC	3721	-1355
BKC	3964	-1598
Marmaton	4066	-1700
Conglomerate	4160	-1794
Arbuckle	4195	-1829

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Surface Pipe	12 1/4	8 5/8	20	223.56	Common	150	2%Gel & 3%CC
Production St.	7 7/8	5 1/2	14	4240.18	EA/2	150	
				DV Tool @ 1766	SMDC	180	

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	3898-3904	500 gal MCA - 1500 gal. 15% NE	3898

TUBING RECORD	Size	Set At	Packer At	Liner Run
				<input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr.	Producing Method	Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
11-01-03	<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		60	0	0	0/100	24

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled

Production Interval Other (Specify) _____

ALLIED CEMENTING CO., INC. 14514

ORIGINAL

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
K

DATE <u>9-24-03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>6:45pm</u>	JOB START	JOB FINISH <u>7:45pm</u>
LEASE <u>HONAS</u>	WELL # <u>1-29</u>	LOCATION <u>RIGA 3 S 2 W 345 EASTO</u>			COUNTY <u>TREGO</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR DISCOVERY #1

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4 T.D. 224

CASING SIZE 8 5/8 DEPTH 224

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. 10-15'

PERFS. _____

DISPLACEMENT 13 1/4 RBL

EQUIPMENT _____

PUMP TRUCK CEMENTER MARK

345 HELPER DAVE

BULK TRUCK _____

222 DRIVER GARY

BULK TRUCK _____

_____ DRIVER _____

OWNER _____

CEMENT AMOUNT ORDERED 150 COM 3% CC 2% CC

COMMON	<u>150</u>	@	<u>7.15</u>	<u>1072.50</u>
POZMIX		@		
GEL	<u>3</u>	@	<u>10.00</u>	<u>30.00</u>
CHLORIDE	<u>5</u>	@	<u>30.00</u>	<u>150.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>150</u>	@	<u>4.15</u>	<u>622.50</u>
MILEAGE	<u>5¢/sk/mile</u>			<u>300.00</u>

RECEIVED
MAR 22 2004
TOTAL 1725.00

REMARKS: KCC WICHITA SERVICE

CEMENT CIRC

CHARGE TO: DOWNING - NELSON

STREET _____

CITY _____ STATE _____ ZIP _____

DEPTH OF JOB _____

PUMP TRUCK CHARGE 520.00

EXTRA FOOTAGE @ _____

MILEAGE 40 @ 3.50 140.00

PLUG 8 5/8 wood @ 45.00

TOTAL 705.00

FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

@ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas ALM

Thomas ALM
PRINTED NAME



CHARGE TO: *Downing & Nelson*
 ADDRESS: _____
 CITY, STATE, ZIP CODE: _____

RECEIVED
 MAR 22 2004
 KCC WICHITA

TICKET No. 6028

PAGE 1 OF 2

1. SERVICE LOCATIONS: *Hayes, Ky* WELL/PROJECT NO.: *1-29* LEASE: *Henas* COUNTY/PARISH: *Trepps* STATE: *Ky.* CITY: _____ DATE: *10-1-03* OWNER: *Same*

2. TICKET TYPE: SERVICE SALES CONTRACTOR: *Discourcy Drfg.* RIG NAME/NO.: _____ SHIPPED VIA: *CIT* DELIVERED TO: *Location* ORDER NO.: _____

3. WELL TYPE: *Oil* WELL CATEGORY: *Development* JOB PURPOSE: *Cmt. 5 1/2" Prod. Csg.* WELL PERMIT NO.: _____ WELL LOCATION: _____

4. REFERRAL LOCATION: _____ INVOICE INSTRUCTIONS: _____

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE		AMOUNT	
		LOC	ACCT	DF									
575		1			MILEAGE #103	40	mil			2	50	100	00
579		1			Pump Service	1	ea			1,500	00	1,500	00
407		1			Insert Float Shoe	1	ea	5 1/2	in	230	00	230	00
408		1			D.W + Plug Set	1	ea			2,150	00	2,150	00
402		1			Centralizers	7	ea			44	00	308	00
403		1			Basket	1	ea			125	00	125	00
193		1			Rotating head	1	ea			150	00	150	00
281		1			Mud Flush	500	gal			60	00	300	00
221		1			RCL	4	gal			19	00	76	00
		1			See Continuation							4259	46

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *Tom K*

DATE SIGNED: _____ TIME SIGNED: _____ A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				9,198 46
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TAX 354 98
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL 9553 44

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

APPROVAL

Thank You!

WELL NO. 1-79

LEASE Honas

JOB TYPE Long String

TICKET NO. 6028

PART NO.	TIME	RATE (BPM)	VOLUME (BBB) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TJBING	CASING	
	0300							On Loss
	0530							Rig laying down D.P. Start in hole with 5 1/2" 14# csg. Cord on #1, #3, #5, #7, #10, #13, #58 Basket on #59
	0700							D.V. on top #59 @ 1766'
	0780							Drop Ball
	0750							Circulate & Rotate Csg.
			12					Plug mouse hole & Rat Hole Pump 500 gal Mud Flush Pump 20 ^{SS} RCL Flush MIX 150 lbs EA-2 cut Finished mixing
			36					wash pump & line
	0810							Displace shut off Plug 54 ^{SS} Mud 49 ^{SS} Mud
	0830		103				1200	Plug down 1200 psf holding Release press. Float Held
	0845						1,100	Drop opening plug open D.V. 1,100 psf pump 20 ^{SS} RCL Flush MIX 180 lbs SMO Finished mixing
			100					Displace closing Plug
	0820		43				1,500	Plug down 1500 psf holding Release press. Dried up wash and rack up track Jobs Complete

RECEIVED

MAR 22 2004

KCC WICHITA

Handwritten signature and initials, possibly 'JC' and 'dy'.