

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 009-24,722-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056
(Owner/Company Name) (Operator's)
Address: 9431 E. Central, Suite 100, Wichita, Kansas 67206 City: Wichita
State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216
Lease: MEYER Well #: 3-33 Sec. 33 Twp. 20S S. R. 11W East West
NE - SW - SW Spot Location / QQQQ County: Stafford Barton

905 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
825 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 266' Cemented with: 225 Sacks
Production Casing Size: 5-1/2" Set at: 3452' Cemented with: 325 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3395' - 97' & 99', 3405' - 07', 10', 12', 15', 16', & 3418'

Elevation: 1796' (G.L. / K.B.) T.D.: 3540' PBTD: 3490' Anhydrite Depth: 551'

Condition of Well: Good Poor Casing Leak Junk in Hole

(Stone Corral Formation)
RECEIVED
KANSAS CORPORATION COMMISSION

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC specifications

JUL 19 2007

CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Rob Long Phone: (620) 793 - 0915

Address: Box 308, 709 E. Santa Fe City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 19, 2007 Authorized Operator / Agent: Loveness Mpanje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Meyer 3-33

LOCATION: 85' S & 165' W of Ne Sw Sw
API: 15-009-24722-0000

Section 33 T 20s R 11w
Barton County, Kansas

OWNER: F.G. Holl Company, L.L.C.

CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 24-Oct-01

COMPLETED: 02-Nov-01

TOTAL DEPTH: **DRILLER** 3540 FEET
LOGGER 3542 FEET

Ground Elevation: 1787

KB Elevation: 1796

LOG

0 -	5 FEET	Top Sand
5 -	31 FEET	Clay
31 -	50 FEET	Fine sand
50 -	70 FEET	Clay
70 -	193 FEET	Sand and Gravel
193 -	567 FEET	Redbeds
567 -	580 FEET	Anhydrite (Driller's)
580 -	1525 FEET	Redbeds, Shales and Salt
1525 -	3465 FEET	Limestone, Shale and Dolomite
3465 -	3540 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 10:00 am on 10/24/01. Drilled 12-1/4" hole to 265'. Ran 6 joints of new 23# 8-5/8" surface casing, tally 248.29' set at 252' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate. Plug down at 3:45 pm on 10/24/01 by Acid Services.

Plugging Report

Ran 84 joints (37 used/47 new) of 14.5# 4-1/2" casing. Tally 3510' and set at 3521' KB. Cemented with 150 sacks 50/50 Poz and 25 sacks A-Serv. Plug down at 3:45am on 11/2/01 by Acid Services, ticket #4199. Centralizers on jts 1,2,3,4 and 5. Basket on #2. Plug Rathole w/15 sx.

DEVIATION SURVEYS

1	degree(s) at	265	feet
3/4	degree(s) at	3183	feet
3/4	degree(s) at	3433	feet
1	degree(s) at	3540	feet

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 19 2007

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

July 30, 2007

Re: MEYER #3-33
API 15-009-24722-00-00
33-20S-11W, 905 FSL 825 FWL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550