

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 185-~~23,067-0000~~ 22718-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056

Address: 9431 E. Central, Suite 100, Wichita, Kansas 67206 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: ( 316 ) 684 - 8481, Ext. 216

Lease: SMITH ESTATE "A" Well #: 5-17 Sec. 17 Twp. 21S S. R. 11W  East  West

SW SW NE Spot Location / QQQQ County: Stafford

2970 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 273' Cemented with: 225 Sacks

Production Casing Size: 4-1/2" Set at: 3548' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3418'-3423'

Elevation: 1791' ( G.L. /  K.B.) T.D.: 3550' PBTD: 3460' Anhydrite Depth: 546'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): \_\_\_\_\_

Heavy mud, hulls, cement and plug according to KCC specifications

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 19 2007

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Rob Long Phone: ( 620 ) 793 - 0915

Address: Box 308, 709 E. Santa Fe City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: ( 620 ) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: July 19, 2007 Authorized Operator / Agent: Loveness Mpanje  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG ----- Smith Estate A 5-17  
located: SW SW NE, Section 17-T21S-R11W, Stafford Co., Ks.

OPERATOR: F. G. Holl Comapny

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 15, 1990

COMPLETED: September 22, 1990

## LOG

0 - 180' Surface soil & sand  
180 - 275' Redbed  
275 - 510' Redbed & shale  
510 - 561' Lime & shale  
561 - 580 Anhydride  
580 - 3550' Lime & Shale

## CASING RECORD

Ran 6 joints 8 5/8" 23# new casing.  
260.23' pipe set at 273' KB. Cemented  
with 225 sacks 60/40 Pozmix W/ 2% gel,  
3% cc. Plug down at 11:00AM 9-15-90  
Good returns to surface by Howco.

Ran 91 joints 4½" 10.5# used casing.  
3537.73' set at 3548' KB. Cemented W/  
500 gallons of superflush and 20 bbls  
salt flush ahead of 100 sacks of Lite  
cement & 125 sacks F. G. Holl mix. Plug  
down at 11:50 PM 9-21-90 by Howco.  
Centralizers on joints 1,6,11,&14  
Shoe joint 12.01'.

## DEVIATION SURVEY

3310' - 3/4°

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 19 2007

CONSERVATION DIVISION



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

July 30, 2007

Re: SMITH ESTATE A #5-17  
API 15-185-22718-00-01  
17-21S-11W, 2970 FSL 2310 FEL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888