

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 047-21,383 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. (Owner / Company Name) KCC License #: 5056 (Operator's)

Address: 9431 E. Central, Suite 100, Wichita, Kansas 67206 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216

Lease: GREEN Well #: 2-5 Sec. 5 Twp. 24S S. R. 17W East West

C - NE - NW Spot Location / QQQQ County: Edwards

4620 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3135 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 320' Cemented with: 225 Sacks

Production Casing Size: 4-1/2" Set at: 4529' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4366' - 4374'

Elevation: 2120' (G.L. / K.B.) T.D.: 4530' PBTD: 4502' Anhydrite Depth: 1170' (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hulls, cement and plug according to KCC specifications

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 19 2007

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Rob Long Phone: (620) 793 - 0915

Address: Box 308, 709 E. Santa Fe City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 19, 2007 Authorized Operator / Agent: Loveness Mpanje (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG

Green # 2-5

located 165' E of C-NE-NW Section 5, T 21S R 17W,
Edwards County, Kansas

OWNER: F.G.Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 15, 1991

COMPLETED: June 21, 1991

TOTAL DEPTH: 4530' Driller
4529' Log

LOG

0 - 250	Surface Soil & Sand
250 - 322	Shale
322 - 1170	Shale & Redbed
1170 - 1190	Anhydrite
1190 - 4530	Lime & Shale

CASING RECORD

Spud at 8:00 a.m. 6-15-91
Drilled 322' of 12 1/4" hole, Ran
7 joints of 8 5/8" 23# new casing
307.56' pipe set at 320' K.B. cemented
with 225 sx's 60/40 pozmix with 2% Gel.
and 3% CC. Plug down at 1:00 p.m. 6-15-91
by B.J.Titan, Good returns to surface.

Ran 110 joints of new & used 4 1/2" 10.5#
new & used casing 4517.54 pipe, Set at 4529'
K.B. cemented with 20 BBL of saltflush and
500 Gal. superflush ahead of 100 sx's of lite
cement and 125 sx's of F.G.Holl mix. Plug
down at 3:30 p.m. 6-22-91 by Howco, Inc.
Centralizers on joints 1-3-5-9 & 13. Shoe
joint 11.06'. 15 sx's cement in rathole.

Deviation Survey: 3/4° at 4341'

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 19 2007

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

July 30, 2007

Re: GREEN #2-5
API 15-047-21383-00-00
5-24S-17W, 4620 FSL 3135 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888