

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 047-21,197 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056
(Owner/Company Name) (Operator's)
Address: 9431 E. Central, Suite 100, Wichita, Kansas 67206 City: Wichita
State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216
Lease: LUNZ "B" Well #: 1-21 Sec. 21 Twp. 24S S. R. 16W East West
- NW - SW - SE Spot Location / QQQQ County: Edwards

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 265' Cemented with: 210 Sacks

Production Casing Size: 4-1/2" Set at: 4450' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4291' - 4295'

Elevation: 2086' (G.L. / K.B.) T.D.: 4454' PBTD: 4418' Anhydrite Depth: 1088'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):
Heavy mud, hulls, cement and plug according to KCC specifications

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 19 2007

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

CONSERVATION DIVISION
WICHITA, KS

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Rob Long Phone: (620) 793 - 0915

Address: Box 308, 709 E. Santa Fe City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 19, 2007 Authorized Operator / Agent: Loveness Mpanje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - LUNZ "B" 1-21

Located: NW SW SE, Section 21-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 9, 1984

COMPLETED: August 15, 1984

TOTAL DEPTH: 4455'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing. 253.02' pipe set at 265' K.B.
90 - 268 Shale	Cemented with 210 sacks 60/40 Pozmix, 3% cc. Plug down at 5:15 PM, 8-9-84, by Howco.
268 - 1090 Shale, Sand, Red Beds	
1090 - 1107 Anhydrite	
1107 - 1890 Shale, Lime Stringers	
1890 - 4270 Lime and Shale	
4270 - 4320 Mississippi	
4320 - 4455 Lime and Shale	Ran 110 joints 4 1/2", 10.5# casing. 11 joints were used. 4440.79' pipe set at 4450' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix plus our regular additives. Plugged rat hole and water well. Plug down at 9:15 AM, 8-15-85, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 19 2007

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1 1/4° at 2082'
3/4° at 4320'



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

July 30, 2007

Re: LUNZ B #1-21
API 15-047-21197-00-00
21-24S-16W, 990 FSL 2310 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888