

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-23,070-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____ .

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056

Address: 9431 E. Central, Suite 100, Wichita, Kansas 67206 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216

Lease: SLEEPER TRUST Well #: 1-10 Sec. 10 Twp. 21S S. R. 11W East West

- N/2 - N/2 - NW Spot Location / QQQQ County: Stafford

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1250 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 266' Cemented with: 225 Sacks

Production Casing Size: 5-1/2" Set at: 3452' Cemented with: 325 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3129' - 3359'

Elevation: 1786' (G.L. / K.B.) T.D.: 3460' PBTD: 3411' Anhydrite Depth: 505'

(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Heavy mud, hulls, cement and plug according to KCC specifications

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

JUL 19 2007

If not explain why? _____ CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Rob Long Phone: (620) 793 - 0915

Address: Box 308, 709 E. Santa Fe City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 19, 2007 Authorized Operator / Agent: Loveness Mpanje (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Sleeper Trust 1-10

LOCATION: 70' W of C N/2 N/2 NW
API: 15-185-230700000

Section 10 T 21s R 11w
Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 05-Jan-98
COMPLETED: 13-Jan-98

TOTAL DEPTH: **DRILLER** 3459 FEET
LOGGER 3454 FEET

Ground Elevation: 1777
KB Elevation: 1786

LOG

0 -	200 FEET	Top Soil and Sand
200 -	471 FEET	Shale
471 -	494 FEET	Anhydrite
494 -	3459 FEET	Limestone, Shale and Dolomite

CASING RECORDS

Spud @ 8:00 am on 01-05-98. Drilled 12-1/4" hole to 270'. Ran 6 joints of 20# 8-5/8" surface casing 250.47' set at 266' KB. Cemented with 225 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 1:45 pm on 01-05-98 by HOWCO. Good returns. Ticket # 308195.

Ran 81 joints of new(2920') & used(523.62') 5-1/2" casing. 3443.62' set at 3452' KB. Cemented with 50 sacks lite & 275 sacks F.G. Holl mix. Plug down at 3:15pm by HOWCO #308200. Centralizers on jts # 1-4-7-9-21. Plug rathole with 15 sacks, and mousehole with 10 sacks. Basket on #19.

DEVIATION SURVEYS

1/2 degree(s) at	270	feet
1/2 degree(s) at	2310	feet
2-1/4 degree(s) at	3145	feet
1-1/4 degree(s) at	3300	feet
1-1/4 degree(s) at	3459	feet



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

July 30, 2007

Re: SLEEPER TRUST #1-10
API 15-185-23070-00-00
10-21S-11W, 330 FNL 1250 FWL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888