

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 175-00113 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 2/10/1962

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334

Address: P.O. Box 18496 (Owner / Company Name) City: Oklahoma City (Operator's)

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375

Lease: E D Fair B Well #: 1-34 Sec. 34 Twp. 31 S. R. 33 East West

C - NE Spot Location / QQQQ County: Seward

3960 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 722' Cemented with: 600 Sacks

Production Casing Size: 5 1/2" Set at: 6020' Cemented with: 210 sx & 110 sx Sacks

List (ALL) Perforations and Bridgeplug Sets: St. Louis (5,870' - 5,872'), CIBP @ 5,830', Chester (5,720' - 5,728'), Marmaton/Cherokee (4,942' - 4,948')

Elevation: 2,884' (G.L. / K.B.) T.D.: 6,200' PBTD: 5,830' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump 500 lbs cotton seed hulls and 25 sx cement. PU and spot 50 sx cement plug @ 3,000'. Perforate 4 holes @ 625'. Squeeze with 25 sx of cement. Tie onto 8 5/8" x 5 1/2" annulus and pump 50 sx.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 31 2007

CONSERVATION DIVISION
KANSAS CORPORATION COMMISSION

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff Phone: (620) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____ (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/30/07 Authorized Operator / Agent: Doug Howeth, By Aletha M. Dewbre-King (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Aletha M. Dewbre-King
Regulatory Analyst

July 30, 2007

VIA UNITED PARCEL SERVICE

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

Re: E D Fair B 1-34
34-31S-33W
Seward Co., KS
API #15-175-00113


Dear Sir or Madam:

Enclosed is a CP-1 form for the referenced well.

If additional information is required, please contact me at the telephone number or e-mail address below.

Sincerely,

Chesapeake Operating, Inc.



Aletha M. Dewbre-King

Enclosures

xc (via e-mail): Kansas Plugging Distribution List

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 31 2007

CONSERVATION DIVISION
WICHITA, KS



Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73154-0496

August 01, 2007

Re: FAIR B #1-34
API 15-175-00113-00-00
34-31S-33W, 1320 FNL 3960 FWL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888