

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 113 - 01288 - 0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 10/20/56

Well Operator: Bruce Oil Co. LLC KCC License #: 5610  
(Owner / Company Name) (Operator's)

Address: 1704 Limestone Rd. City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: ( 620 ) 241 - 2938

Lease: Koehn "B" Well #: 4 Sec. 34 Twp. 19 S. R. 2  East  West

Approx - SW - SW - NE Spot Location / QQQQ County: McPherson

2970 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 2510 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # E-26,505  ENHR Docket # E 26505  Other: \_\_\_\_\_

Conductor Casing Size: N/A Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 168 Cemented with: 100 Sacks

Production Casing Size: 5 1/2 Set at: 2964 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations 2947-2967 W/ 45 Holes

Elevation: 1544 ( G.L. /  K.B.) T.D.: 2972 P.B.T.D.: 2962 Anhydrite Depth: N/A  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off bottom and perforations to 2900', put in 5 sacks cement.

Rip pipe off at 300', pull pipe, build bridgeplug, and cement well to surface with cement slurry.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? N/A

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lonny Bruce

Phone: ( 620 ) 241 - 2938

Address: 1704 Limestone Rd. City / State: McPherson, KS

Plugging Contractor: Sunflower Well Service KCC License #: 30280  
(Company Name) (Contractor's)

Address: P.O. Box 341, Canton, KS 67428 Phone: ( 620 ) 628 - 4723

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/26/07 Authorized Operator / Agent: Lonny Bruce (Signature)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 27 2007

CONSERVATION DIVISION  
WICHITA, KS

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BRUCE OIL COMPANY, L.L.C.  
1704 LIMESTONE RD  
MCPHERSON, KS 67460-6500

July 31, 2007

Re: KOEHN B #4  
API 15-113-01288-00-01  
34-19S-2W, 2970 FSL 2310 FEL  
MCPHERSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000