

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-073-19674-0001
API # 15 - Prior to 1967 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 11-15-1938 (Spud date)

Well Operator: CROSS BAR ENERGY, LLC KCC License #: 33245
(Owner / Company Name) (Operator's)

Address: PO BOX 400 City: VALLEY CENTER

State: KANSAS Zip Code: 67147-0400 Contact Phone: (316) 799 - 2933

Lease: BURKETT "C" Well #: CW-9 Sec. 24 Twp. 23 S. R. 10 ☒ East ☐ West

C - SW - NE - NW Spot Location / QQQQ County: GREENWOOD

4290 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

3630 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well

☐ SWD Docket # _____ ☒ ENHR Docket # E-749 ☐ Other: _____

Conductor Casing Size: (Surface) 10" Set at: 1030' Cemented with: N/A Sacks

Surface Casing Size: (Production) 7" Set at: 2137' Cemented with: 125 (circulated to surface) Sacks

Production Casing Size: (Prod Liner) 5 1/2" Set at: 2137' Cemented with: 100 (circulated to surface) Sacks

List (ALL) Perforations and Bridgeplug Sets: 2072'; 2078'; 2082'; 2085'; 2088'; 2103'; 2107'; 2110'; 2112'; 2114'; (One shot each foot)

Elevation: 1252 (☒ G.L. / ☐ K.B.) T.D.: 2137' PBTD: 2136' Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: ☐ Good ☐ Poor ☐ Casing Leak ☒ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Spot plugs down 2 7/8" TBG AS FOLLOWS:

20 sxs @ 1705'; 20 sxs @ 900'; 15 sxs @ 150' to surface

Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

ANDREW BRENSING Phone: (620) 437 - 6099

Address: PO BOX 44 City / State: MADISON, KS 66860

Plugging Contractor: PRATT WELL SERVICE, INC. KCC License #: 5893
(Company Name) (Contractor's)

Address: PO BOX 847, PRATT, KANSAS 67124 Phone: (620) 672 - 2531

Proposed Date and Hour of Plugging (if known?): 8-22-2006 8:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-20-2006 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well already plugged - KCC-DK

RECEIVED
OCT 19 2006
KCC WICHITA

CONSOLIDATED OIL WELL SERVICES, INC.
P.O. BOX 884, CHANUTE, KS 66720
620-431-9210 OR 800-467-8676

TICKET NUMBER 10577
LOCATION Eureka
FOREMAN Troy Strickler

TREATMENT REPORT & FIELD TICKET
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-22-06	0598	C+W #9 Burkett				GW
CUSTOMER Cross Bar Energy						
MAILING ADDRESS P.O. Box 400						
CITY Valley Center	STATE KS	ZIP CODE				
			TRUCK #	DRIVER	TRUCK #	DRIVER
			446	Calin		
			442	Jim		
			436	J.P.		

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 5 1/2"
CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 14" SLURRY VOL _____ WATER gal/sk 7.0 CEMENT LEFT in CASING _____
DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____
REMARKS: Safety Meeting. Rig up to 2 3/8" tubing. Follow Plug Orders.

20skt @ 1705'
20skt @ 900'
15skt 150' to surface

60/40 Poz-mix Cement
4% Gel

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	525.00	525.00
5406	15	MILEAGE	3.15	47.25
1131	55skt	60/40 Poz-Mix Cement	9.35	514.25
1118A	190*	Gel 4%	.14*	26.60
5407		Ton-Mileage Bulk Truck	m/c	275.00
5502C	4hrs	80Bbl Vac Truck	90.00	360.00
1123	300gal	City Water	12.80	38.40
RECEIVED				
OCT 19 2006				
KCC WICHITA				
Thank You!				
			Sub Total	1786.50
			6.38 SALES TAX	36.59
			ESTIMATED TOTAL	1823.00

008359

AUTHORIZATION Witnessed by Ray

TITLE _____

DATE _____



CONSOLIDATED
OIL WELL
SERVICES INC.
AN INFINITY COMPANY

REMIT TO
Consolidated Oil Well Services, Inc.
Dept. 1228
Denver, CO 80256

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 208359

Invoice Date: 08/23/2006 Terms:

Page 1

CROSS BAR ENERGY
P.O. BOX 400
VALLEY CENTER KS 67147-0400
(316)799-2931

BURKETT C&W #9
10577
08-22-06

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	55.00	9.3500	514.25
1118A	S-5 GEL/ BENTONITE (50#)	190.00	.1400	26.60
1123	CITY WATER	3000.00	.0128	38.40

Description	Hours	Unit Price	Total
436 80 BBL VACUUM TRUCK (CEMENT)	4.00	90.00	360.00
442 MIN. BULK DELIVERY	1.00	275.00	275.00
446 P & A OLD WELL	1.00	525.00	525.00
446 EQUIPMENT MILEAGE (ONE WAY)	15.00	3.15	47.25

Lease 5-11-06
Well # 51119
Desc. 51119
Acct # 150-10

RECEIVED
OCT 19 2006
KCC WICHITA

Parts:	579.25	Freight:	.00	Tax:	36.50	AR	1823.00
Labor:	.00	Misc:	.00	Total:	1823.00		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____

BARTLESVILLE, OK
P.O. Box 1453 74005
918/338-0808

EUREKA, KS
820 E. 7th 67045
620/583-7664

OTTAWA, KS
2631 So. Eisenhower Ave. 66067
785/242-4044

GILLETTE, WY
300 Enterprise Avenue 82716
307/686-4914

THAYER, KS
8655 Dorn Road 66776
620/839-5269